

URBAN
80% FED.
20% STATE

SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
						ROADWAY 0004 RURAL	BRIDGE 0011 RURAL		
		44004250	PAVED SHOULDER REMOVAL	SQ YD	387	387			
		44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	127	127			
		44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	24	24			
		48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	648	648			
		48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	90	90			
		48203031	HOT-MIX ASPHALT SHOULDERS, 8-1/2"	SQ YD	124	124			
		48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	2,928	2,928			
	*	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
		50105220	PIPE CULVERT REMOVAL	FOOT	82	82			
		50200100	STRUCTURE EXCAVATION	CU YD	122		122		
		50300225	CONCRETE STRUCTURES	CU YD	63.7		63.7		
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	268.4		268.4		
		50300260	BRIDGE DECK GROOVING	SQ YD	626		626		
		50300280	CONCRETE ENCASEMENT	CU YD	6.2		6.2		
		50300300	PROTECTIVE COAT	SQ YD	724		724		
		50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.	FOOT	516.5		516.5		
	*	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	71,230		71,230		
		50800515	BAR SPLICERS	EACH	646		646		
		51201600	FURNISHING STEEL PILES HP12X53	FOOT	888		888		
	*	51202305	DRIVING PILES	FOOT	888		888		
		51203600	TEST PILE STEEL HP12X53	EACH	2		2		
		51500100	NAME PLATES	EACH	1		1		
		54215553	METAL END SECTIONS 18"	EACH	2	2			
		54215775	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2			
		542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	63	63			
		542D5485	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	46	46			
		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	104		104		
		60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	5	5			
	*	60100915	PIPE DRAINS 6"	FOOT	50	50			
	*	60100925	PIPE DRAINS 8"	FOOT	50	50			
	*	60107600	PIPE UNDERDRAINS 4"	FOOT	528	528			
		60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3.7	3.7			

FILE NAME = P:\CBBEL WEST Projects\2009\05-0147_IL173_Cvt1\09m\Shr\A\160129-shr-50102.dgn



USER NAME = #USER#	DESIGNED - SBP/KMA	REVISED -
	DRAWN - NDP	REVISED -
PLOT SCALE =	CHECKED - PJF	REVISED -
PLOT DATE = 1/6/2011	DATE - 12/14/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 4 OF 106 SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION 132 B-2	COUNTY McHENRY	TOTAL SHEETS 106	SHEET NO. 4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60I29	