

URBAN
80% F&O
20% STATE

CONSTRUCTION CODE

SPECIALTY ITEM	SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
						ROADWAY 0004 RURAL	BRIDGE 0011 RURAL			
	*	61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	2				
S		63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,087.5	1,087.5				
S		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4				
S	*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4				
		63200310	GUARDRAIL REMOVAL	FOOT	441	441				
		63500105	DELINEATORS	EACH	41	41				
		64200105	SHOULDER RUMBLE STRIPS	FOOT	3,429	3,429				
		66500105	WOVEN WIRE FENCE, 4'	FOOT	454	454				
		66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	20	20				
	*	66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2				
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10				
		67100100	MOBILIZATION	L SUM	1	1				
		70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1				
		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14				
	*	70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1				
	*	70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6				
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4				
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,208	1,208				
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,638	10,638				
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	80	80				
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,740	1,740				
		70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,925	1,925				
		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,830	1,830				
		70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	87.5	87.5				
		70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2				
S		72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2				
S		78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	9,240	9,240				
S		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	82	82				
S		78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6				

FILE NAME = P:\CIBBEL WEST P-co\pco\2009\05-0147_IL173\Civil\Dgn\Shx\Di660125-nt-50003.dgn



USER NAME = #USER#	DESIGNED - SBP/KMA	REVISED -
	DRAWN - NDP	REVISED -
PLOT SCALE =	CHECKED - PJF	REVISED -
PLOT DATE = 1/6/2011	DATE - 12/14/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 5 OF 106 SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION 132 B-2	COUNTY McHENRY	TOTAL SHEETS 106	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60I29	