

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	O/S (LT)	O/S (RT)	COMMENTS
12	431+80.00	40		MS - 6", 6"
8	432+05.00	40		8.0
12	432+11.00	40		MS-7.5", 4.5"
12	432+12.00	35		MS-6", 6"
7.5	432+30.00	35		7.5
9.0	432+40.00	30		9.0
13.5	432+45.00	38		13.5
18.5	432+55.00		38	MS- 9", 9.5"
12	432+65.00		38	MS- 7", 5"
7.0	432+70.00	35		7.0
16.5	432+82.00		40	MS- 12.5", 4"
6.0	432+85.00	37		6.0
15.5	433+20.00		42	MS- 8.5", 7"
13.5	433+24.00		39	MS- 7", 6.5"
6	433+30.00		39	6.0
14.5	433+35.69		39.4	14.5
8	433+47.00		38	8.0
23.5	435+55.00		42	MS-13", 10.5"
12	435+63.00		45	12.0
9.5	435+72.00		50	9.5
8	435+75.00		45	8.0
13.0	435+85.00		50	13.0
12.0	435+87.00		45	12.0
8.0	435+93.00		50	8.0
11.5	435+95.00		48	MS- 6", 5.5"
22.5	435+98.00		45	MS- 7.5", 7.5", 7.5"
8.5	436+14.00		44	8.5
8.0	436+30.00		44	8.0
13.0	436+55.00		44	13.0
6.5	436+61.00		50	6.5
21.5	436+72.00		44	MS- 14", 7.5"
8.0	436+77.00		50	8.0
13.0	436+86.00		42	13.0
7.5	436+92.00		50	7.5
10.0	437+08.00		48	10.0
6.0	437+20.00		50	6.0
6.5	437+28.00		47	6.5
12.0	437+35.00		48	12.0
26	438+10.00	36		MS- 5.5", 6", 5", 5", 3.5"
6	440+29.08	35.0		6.0
12.0	443+69.24		55.3	12.0
5.0	443+72.00		59	5.0
6	444+00.00	35		6
6.5	444+65.00		53	6.5
7.0	444+72.00		55	7.0
12.0	446+15.00		55	12.0

513 TOTAL

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	O/S (RT)	SIZE (IN.)	REMARKS
15.5	437+35.00	43	15.5	
17.5	444+44.84	56.9	17.5	
20.5	447+20.00	52	20.5	

54 TOTAL

20800150 TRENCH BACKFILL

LOCATION	DESCRIPTION	LENGTH (FT)	WIDTH (FT)	DEPTH (FT)	VOLUME (CU YD)
435+14.14	30" EQ. ROUND SIZE CULVERT	20.0	4.5	1.4	4.7
443+90	18" DIA CULVERT	20.0	3.0	2.9	6.4

TOTAL 12.0

21301052 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION	TO	REMARKS
100	935+80.00	950+92.00	AS DIRECTED BY R.E.

100 TOTAL

44000500 COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION	TO	REMARKS
61	LT. STA.	444+38.80	444+98.90
457	RT. STA.	444+98.90	449+55.90

518 TOTAL

44004000 PAVED DITCH REMOVAL

FOOT	LOCATION	TO	REMARKS
374	LT. STA.	431+16.60	434+89.80
448	RT. STA.	431+41.60	435+89.03
152	LT. STA.	435+34.10	436+85.30
10	LT. STA.	442+40.62	442+50.00
192	LT. STA.	442+50.00	444+41.65
379	RT. STA.	442+88.22	446+66.62

1555 TOTAL

50105220 PIPE CULVERT REMOVAL

FOOT	LOCATION	TO	REMARKS
45	LT. STA.	434+89.80	435+34.10 DRIVEWAYS
37	RT. STA.	442+52.30	442+89.30

82 TOTAL

54215553 METAL END SECTIONS 18"

EACH	LOCATION	RT	REMARKS
1	443+49.92	RT	
1	444+16.09	RT	

2 TOTAL

54215775 METAL END SECTIONS, EQUIVALENT ROUND-SIZE 30"

EACH	LOCATION	LT	REMARKS
1	434+84.34	LT	
1	435+38.63	LT	

2 TOTAL

542D1063 PIPE CULVERTS, CLASS D, TYPE 2 18"

FOOT	LOCATION	REMARKS
63	443+90	LOCATED AT ENTRANCE

63 TOTAL

542D5485 PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"

FOOT	LOCATION	LT	REMARKS
46	435+14.1	LT	LOCATED AT DRIVEWAY

46 TOTAL

FILE NAME = P:\CBBEL\WEST\Projects\2080150\Drawings\2080150.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = #USER#	DESIGNED - SBP/KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/5/2011	CHECKED - PJF	REVISED -
	DATE - 12/14/10	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 9	OF 106 SHEETS	STA. TO STA.

F.A.P. RTE. 303	SECTION 132 B-2	COUNTY MCHENRY	TOTAL SHEETS 106	SHEET NO. 9
CONTRACT NO. 60129				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				