

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	REMARKS
1	40.62' LT. STA. 439+11.57	RM1
1	48.5' LT. STA. 439+11.88	RM2
1	48.5' LT. STA. 441+01.59	RM3
1	41.27' LT. STA. 441+01.59	RM4
1	41.38' LT. STA. 441+70.81	RM5
1	63.50' LT. STA. 441+70.81	RM6
1	63.50' LT. STA. 444+89.60	RM7
1	41.12' LT. STA. 444+89.60	RM8
1	39.60' RT. STA. 435+50.00	RM9
1	53.50' RT. STA. 435+50.00	RM10
1	53.50' RT. STA. 438+50.00	RM11
1	58.50' RT. STA. 438+50.00	RM12
1	58.50' RT. STA. 441+03.22	RM13
1	38.73' RT. STA. 441+03.22	RM14
1	38.62' RT. STA. 441+68.62	RM15
1	58.50' RT. STA. 441+68.62	RM16
1	58.50' RT. STA. 447+75.00	RM17
1	48.50' RT. STA. 447+75.00	RM18
1	48.50' RT. STA. 448+70.00	RM19
1	40.75' RT. STA. 448+70.00	RM20
20	TOTAL	

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	REMARKS
1	CL STA. 438+55.37	PC STATION
1	CL STA. 448+44.54	PT STATION
2	TOTAL	

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

EACH	LOCATION	REMARKS
1	LT./RT. 428+29.00 TO 453+65.00	STAGES 1 AND 2
1	TOTAL	

70106700 TEMPORARY RUMBLE STRIP

EACH	LOCATION	REMARKS
1	STA. 412+80.00	STAGE 1 & STAGE 2
1	STA. 417+80.00	
1	STA. 422+80.00	
1	STA. 458+97.00	
1	STA. 463+97.00	
1	STA. 468+97.00	
6	TOTAL	

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION	REMARKS
238	CL STA. 429+40.00	TO 442+50.00 STAGE 3- DOUBLE 4" SKIP-DASH
104	LT./RT. STA. 429+40.00	TO 442+50.00 STAGE 3 - SINGLE 4" WHITE EDGE (2 SIDES)
182	CL STA. 442+50.00	TO 452+50.00 STAGE 3- DOUBLE 4" SKIP-DASH
80	LT./RT. STA. 442+50.00	TO 452+50.00 STAGE 3 - SINGLE 4" WHITE EDGE (2 SIDES)
604	SUB-TOTAL APPLICATIONS	
1,208	TOTAL	

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	REMARKS
888	LT./RT. STA. 429+80.14	TO 433+50.00 SINGLE EDGE LINE - WHITE STAGE 1
3,600	LT./RT. STA. 433+50.00	TO 448+50.00 SINGLE EDGE LINE - WHITE
831	LT./RT. STA. 448+50.00	TO 451+96.38 SINGLE EDGE LINE - WHITE
888	LT./RT. STA. 429+80.14	TO 433+50.00 SINGLE EDGE LINE - WHITE STAGE 2
3,600	LT./RT. STA. 433+50.00	TO 448+50.00 SINGLE EDGE LINE - WHITE
831	LT./RT. STA. 448+50.00	TO 451+96.38 SINGLE EDGE LINE - WHITE
10,638	TOTAL	

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

FOOT	LOCATION	REMARKS
12	11.5' RT. STA. 429+80.14	STAGE 1- STOP BAR -WHITE
12	LT. STA. 451+96.38	STAGE 1- STOP BAR -WHITE
16	LT. STA. 434+14.14	STAGE 1- STOP BAR -WHITE DRIVEWAY
12	11.5' RT. STA. 429+80.14	STAGE 2- STOP BAR -WHITE
12	LT. STA. 451+96.38	STAGE 2- STOP BAR -WHITE
16	LT. STA. 434+14.14	STAGE 1- STOP BAR -WHITE DRIVEWAY
80	TOTAL	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LENGTH (FT)	WIDTH (INCHES)	SQ FT	LOCATION	REMARKS
222	4	74.0	LT./RT. STA. 429+80.00	TO 432+02.00 REM STG 1 MARKING 4"
228	4	76.0	LT./RT. STA. 449+69.00	TO 451+97.00 REM STG 1 MARKING 4"
2217	4	739.0	LT./RT. STA. 429+80.00	TO 451+97.00 REM STG 2 NORTH SIDE 4"
2217	4	739.0	LT./RT. STA. 429+80.00	TO 451+97.00 REM STG 2 SOUTH SIDE 4"
33	24	66.0	LT./RT. STA. 434+97.00	TO 435+30.00 ENT DRIVE LT STOP BAR
11	24	22.0	LT./RT. STA. 429+80.00	TO 429+80.00 WEST END STOP BAR
12	24	24.0	LT./RT. STA. 451+97.00	TO 451+97.00 EAST END STOP BAR
1,740	TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARKS
112.5	4.0' LT. STA. 431+27.64	TO 432+40.14 TAPER SECTION - STAGE 1
225.0	5.0' RT. STA. 432+40.14	TO 434+67.22 TANGENT SECTION - STAGE 1
100.0	5.0' RT. STA. 434+67.22	TO 435+62.14 TANGENT SECTION - STAGE 2
1,375.0	5.0' RT. STA. 435+62.14	TO 449+30.14 TANGENT SECTION - STAGE 3
112.5	4.0' LT. STA. 449+30.14	TO 450+42.64 TAPER SECTION - STAGE 1
1,925	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARKS
112.5	4.0' LT. STA. 431+27.64	TO 432+40.14 TAPER SECTION - STAGE 1
225.0	5.0' RT. STA. 432+40.14	TO 434+67.22 TANGENT SECTION - STAGE 1
1,375.0	5.0' RT. STA. 435+62.14	TO 449+30.14 TANGENT SECTION - STAGE 1
112.5	4.0' LT. STA. 449+30.14	TO 450+42.64 TAPER SECTION - STAGE 1
1,830	TOTAL	

70500100 TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A

FOOT	LOCATION	REMARKS
75.0	RT SIDE, WEST OF BRIDGE	MAY NOT BE REQUIRED - TO BE FIELD DETERMINED
12.5	RT SIDE, EAST OF BRIDGE	MAY NOT BE REQUIRED - TO BE FIELD DETERMINED
87.5	TOTAL	

FILE NAME = P:\CBBEL\WEST Projects\2009\99-9147_IL173\CV11\09n\SHA\0168129-ent-schedule3.dgn



USER NAME = *USER*	DESIGNED - SBP/KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/5/2011	CHECKED - PJF	REVISED -
	DATE - 12/14/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCALE:		SHEET NO. 11 OF 106 SHEETS		STA. TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	132 B-2	McHENRY	106	11
CONTRACT NO. 60129				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				