

| 70500615 TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1 | | |
|---|-------------------------|--|
| EACH | LOCATION | REMARKS |
| 1.0 | RT SIDE, WEST OF BRIDGE | REQUIRED |
| 1.0 | RT SIDE, EAST OF BRIDGE | MAY NOT BE REQUIRED - TO BE FIELD DETERMINED |
| 2.0 | TOTAL | |

| 72400100 REMOVE SIGN PANEL ASSEMBLY - TYPE A | | |
|--|---------------|---------|
| EACH | LOCATION | REMARKS |
| 1 | RT. 433+99.00 | |
| 1 | RT. 438+54.30 | |
| 2 | TOTAL | |

| 78008210 POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | | | | |
|---|-------------------|----|-----------|--------------------------|
| FOOT | LOCATION | | | REMARKS |
| 2310 | LT. STA 429+40.00 | TO | 452+50.00 | WHITE EDGE LINE |
| 2310 | RT. STA 429+40.00 | TO | 452+50.00 | WHITE EDGE LINE |
| 4620 | CL STA. 429+40.00 | TO | 452+50.00 | DOUBLE YELLOW CENTERLINE |
| 9240 | TOTAL | | | |

| 78100100 RAISED REFLECTIVE PAVEMENT MARKER | | | | |
|--|--------------|----|-----------|--------------------------|
| EACH | LOCATION | | | REMARKS |
| 24 | 429+40.00 | TO | 438+55.40 | 80 FOOT SPACING |
| 12 | 438+55.37 | TO | 440+86.20 | 40 FOOT SPACING ON CURVE |
| 34 | 442+03.80 | TO | 448+44.50 | 40 FOOT SPACING ON CURVE |
| 12 | 448+44.50 | TO | 452+50.00 | 80 FOOT SPACING |
| 82 | TOTAL | | | |

| 78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | | | | |
|---|--------------|----|-----------|--------------------------|
| EACH | LOCATION | | | REMARKS |
| 6 | 440+92.61 | TO | 441+80.20 | 40 FOOT SPACING ON CURVE |
| 6 | TOTAL | | | |

| 78200410 GUARDRAIL MARKERS, TYPE A | | | | |
|------------------------------------|--------------------|----|-----------|-----------------|
| EACH | LOCATION | | | REMARKS |
| 3 | LT. STA. 436+25.00 | TO | 438+55.40 | 80 FOOT SPACING |
| 6 | LT. STA. 438+55.40 | TO | 440+71.50 | 40 FOOT SPACING |
| 3 | RT. STA. 436+25.00 | TO | 438+55.40 | 80 FOOT SPACING |
| 6 | RT. STA. 438+55.40 | TO | 440+73.00 | 40 FOOT SPACING |
| 2 | RT. STA. 441+94.48 | TO | 443+15.70 | 80 FOOT SPACING |
| 6 | LT. STA. 441+88.40 | TO | 444+14.70 | 40 FOOT SPACING |
| 4 | RT. STA. 441+87.20 | TO | 443+15.70 | 40 FOOT SPACING |
| 30 | TOTAL | | | |

| 78200520 BARRIER WALL MARKERS, TYPE B | | | | |
|---------------------------------------|--------------------|----|-----------|----------------------------|
| EACH | LOCATION | | | REMARKS |
| 3 | LT. STA. 440+92.09 | TO | 441+80.73 | 2 MARKERS AT EACH INTERVAL |
| 3 | RT. STA. 440+93.15 | TO | 441+79.67 | |
| 6 | TOTAL | | | |

| 78201000 TERMINAL MARKER - DIRECT APPLIED | | |
|---|--------------------|---------|
| EACH | LOCATION | REMARKS |
| 1 | RT. STA. 443+65.70 | |
| 1 | LT. STA. 444+64.70 | |
| 1 | LT. STA. 435+75.00 | |
| 1 | RT. STA. 435+75.00 | |
| 4 | TOTAL | |

| 78300100 PAVEMENT MARKING REMOVAL | | | | | | |
|-----------------------------------|----------------|------------|--------------|----|-----------|----------------------|
| LENGTH (FEET) | WIDTH (INCHES) | SQ FT | LOCATION | | | REMARKS |
| 260 | 8.0 | 173 | 429+80.00 | TO | 432+40.00 | DOUBLE 4" CENTERLINE |
| 267 | 8.0 | 178 | 449+30.00 | TO | 451+97.00 | DOUBLE 4" CENTERLINE |
| | | 351 | TOTAL | | | |

| 78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | | | | | |
|--|----------------|----|-----------|--|---------|
| EACH | LOCATION | | | | REMARKS |
| 4 | STA. 429+80.00 | TO | 431+30.00 | | |
| 4 | STA. 450+46.00 | TO | 452+00.00 | | |
| 8 | TOTAL | | | | |

| X0549200 CLEANING PAVED DITCH | | | | | |
|-------------------------------|--------------------|----|-----------|--|---------|
| FOOT | LOCATION | | | | REMARKS |
| 340.0 | LT. STA. 431+41.60 | TO | 434+80.78 | | |
| 340.0 | TOTAL | | | | |

| X6063000 CONCRETE GUTTER, TYPE B (SPECIAL) | | | | | |
|--|--------------------|----|-----------|--|---------|
| FOOT | LOCATION | | | | REMARKS |
| 418 | LT. STA. 445+44.00 | TO | 449+62.03 | | |
| 418 | TOTAL | | | | |

| Z0022800 FENCE REMOVAL | | | | | | |
|------------------------|---------------------|----|-----------|--|--|-----------|
| FOOT | LOCATION | | | | | REMARKS |
| 212.4 | LEFT STA. 439+11.50 | TO | 441+23.90 | | | BARB WIRE |
| 251.0 | LEFT STA. 441+49.00 | TO | 444+00.00 | | | |
| 464.0 | TOTAL | | | | | |

| Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | | | | | |
|--|--------------------|--|--|--|----------------------------|
| EACH | LOCATION | | | | REMARKS |
| 1 | LT. STA. 430+95.64 | | | | STAGE 1 BEGINNING OF TAPER |
| 1 | LT. STA. 434+67.00 | | | | STAGE 1 DRIVEWAY ACCESS |
| 1 | LT. STA. 435+62.00 | | | | STAGE 1 DRIVEWAY ACCESS |
| 1 | LT. STA. 450+42.00 | | | | STAGE 1 BEGINNING OF TAPER |
| 4 | TOTAL | | | | |

| Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | | | | | |
|---|---------------------|--|--|--|----------------------------|
| EACH | LOCATION | | | | REMARKS |
| 1 | STA. LEFT 430+95.64 | | | | STAGE 2 BEGINNING OF TAPER |
| 1 | STA. LEFT 450+42.00 | | | | STAGE 2 BEGINNING OF TAPER |
| 2 | TOTAL | | | | |

FILE NAME = P:\CBBEL\WEST\Projects\2009\09-09-04\7_ILIT3\Civil\Ugns\Shk\01680229-int-schedule.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

| | | |
|----------------------|--------------------|-----------|
| USER NAME = #USER# | DESIGNED - SBP/KMA | REVISED - |
| PLOT SCALE = | DRAWN - NDP | REVISED - |
| PLOT DATE = 1/5/2011 | CHECKED - PJF | REVISED - |
| | DATE - 12/14/10 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

| SCHEDULE OF QUANTITIES | | | |
|------------------------|----------------------------|------|---------|
| SCALE: | SHEET NO. 12 OF 106 SHEETS | STA. | TO STA. |
| | | | |

| | | | | |
|---------------------|---------|---------|--------------|---------------------------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 303 | 132 B-2 | McHENRY | 106 | 12 |
| FED. ROAD DIST. NO. | | | | ILLINOIS FED. AID PROJECT |
| CONTRACT NO. 60129 | | | | |