

# PAVEMENT SCHEDULE

LOCATION	OFF.	REMARKS	LENGTH	WIDTH	AREA	35101600	35501308	40603080	40603335	42000411	42001420	42101300	48101500	48102100	48203031	48300410	Z0001050	Z0062456
						AGGREGATE BASE COURSE, TYPE B 4"	HOT-MIX ASPHALT BASE COURSE, 6"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	PROTECTIVE COAT	AGGREGATE SHOULDERS, TYPE B 6"	AGGREGATE WEDGE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS, 8-1/2"	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	AGGREGATE SUBGRADE 12"	TEMPORARY PAVEMENT
			(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
<b>MAINLINE</b>																		
429+80.00 - 432+31.18		HMA	251.18	26	725.63				82									
432+31.18 - 434+88.68		PCC	257.50	26	743.89					743.89		743.89						743.89
434+88.68 - 440+46.16		PCC	557.48	26	1610.50					1610.50		1610.50						1610.50
440+46.16 - 440+56.16		CONNECTOR	10.00	26	28.89						28.89	28.89						28.89
<b>BRIDGE</b>																		
442+03.81 - 442+13.81		CONNECTOR	10.00	26	28.89						28.89	28.89						28.89
442+13.81 - 442+50.00		PCC	36.19	26	104.55					104.55		104.55						104.55
442+50.00 - 449+53.82		PCC	703.82	26	2033.26					2033.26		2033.26						2033.26
449+53.82 - 451+97.00		HMA	243.18	26	702.52				80									
<b>SHOULDERS</b>																		
431+41.60 - 432+31.18	LT	HMA	89.58	6	59.72	64.70			7						59.72			
432+31.18 - 435+29.72	LT	PCC	298.54	6	199.03							199.03				199.03		215.61
435+29.72 - 435+65.72	LT	PCC	36.00	VARIES	36.00							36.00				36.00		38.00
435+65.72 - 436+00.72	LT	PCC	35.00	12	46.67							46.67				46.67		48.61
436+00.72 - 436+08.72	LT	PCC	8.00	VARIES	10.11							10.11				10.11		10.56
436+08.72 - 440+55.20	LT	PCC	446.48	10.75	533.30							533.30				533.30		558.10
<b>BRIDGE</b>																		
442+04.66 - 442+50.00	LT	PCC	45.34	10.75	54.16							54.16				54.16		56.67
442+50.00 - 444+39.10	LT	PCC	189.10	10.75	225.87							225.87				225.87		236.37
444+39.10 - 444+47.22	LT	PCC	8.12	VARIES	10.26							10.26				10.26		10.71
444+47.22 - 444+82.76	LT	PCC	35.54	12	47.39							47.39				47.39		49.36
444+82.76 - 445+19.32	LT	PCC	36.56	VARIES	36.56							36.56				36.56		38.59
445+19.32 - 449+53.82	LT	PCC	434.50	6	289.67							289.67				289.67		313.81
449+53.82 - 450+50.20	LT	HMA	96.38	6	64.25	69.46			7					64.25				
445+01.00 - 445+43.98	LT	PCC OUTLET			19.22							19.22						
445+43.98 - 449+53.82	LT	GUTTER	409.84	1.75	79.69							79.69						84.69
449+53.82 - 449+62.07	LT	PCC OUTLET			2.67							2.67						
<b>SHOULDERS (RT)</b>																		
431+41.60 - 432+31.18	RT	HMA	89.58	6	59.72	64.70			7									
432+31.18 - 435+24.13	RT	PCC	292.95	6	195.30							195.30				195.30		211.57
435+24.13 - 435+60.13	RT	PCC	36.00	VARIES	36.00							36.00				36.00		38.00
435+60.13 - 435+95.13	RT	PCC	35.00	12	46.67							46.67				46.67		48.61
435+95.13 - 436+03.13	RT	PCC	8.00	VARIES	10.11							10.11				10.11		10.56
436+03.13 - 440+57.32	RT	PCC	454.19	10.75	542.50							542.50				542.50		567.74
<b>BRIDGE</b>																		
442+02.86 - 442+50.00	RT	PCC	47.14	10.75	56.31							56.31				56.31		58.92
442+50.00 - 443+33.19	RT	PCC	83.19	10.75	99.37							99.37				99.37		103.99
443+33.19 - 443+40.97	RT	PCC	7.78	VARIES	9.83							9.83				9.83		10.27
443+40.97 - 443+75.45	RT	PCC	34.48	12	45.97							45.97				45.97		47.89
443+75.45 - 444+10.92	RT	PCC	35.47	VARIES	35.47							35.47				35.47		37.44
444+10.92 - 449+53.82	RT	PCC	542.90	6	361.93							361.93				361.93		392.09
449+53.82 - 450+50.20	RT	HMA	96.38	6	64.25	69.46			7									
<b>SHOULDERS (LT)</b>																		
429+80.00 - 434+88.68	LT	AGGREGATE	508.68	VARIES	115.99								115.99					
435+33.82 - 440+55.20	LT	AGGREGATE	521.38	VARIES	57.57								57.57					
442+02.82 - 445+19.62	LT	AGGREGATE	316.80	VARIES	34.52								34.52					
449+62.05 - 451+97.00	LT	AGGREGATE	234.95	VARIES	55.54								55.54					
429+80.00 - 440+57.36	RT	AGGREGATE	1,077.36	VARIES	184.17								184.17					
442+02.82 - 443+79.44	RT	AGGREGATE	176.62	VARIES	19.88								19.88					
444+04.86 - 451+97.00	RT	AGGREGATE	792.14	VARIES	180.15								180.15					
<b>SHOULDERS (RT) - AGG. WEDGE</b>																		
431+41.60 - 434+88.68	LT	AGG. WEDGE	347.08															
435+33.82 - 440+55.00	LT	AGG. WEDGE	521.18															
442+04.80 - 442+50.00	LT	AGG. WEDGE	45.20															
442+50.00 - 445+19.62	LT	AGG. WEDGE	269.62															
449+62.05 - 450+50.00	LT	AGG. WEDGE	87.95															
431+41.60 - 435+30.05	RT	AGG. WEDGE	388.45															
435+30.05 - 440+57.36	RT	AGG. WEDGE	527.31															
442+02.82 - 442+50.00	RT	AGG. WEDGE	47.18															
442+50.00 - 443+78.58	RT	AGG. WEDGE	128.58															
444+04.86 - 450+50.00	RT	AGG. WEDGE	645.14															
<b>ENTRANCES</b>																		
434+84.40	LT	HMA ENT.			62.00	66.00			7									
443+90.00	RT	HMA ENT.			184.00	196.00			21									
444+82.90	LT	HMA ENT.			39.00	42.00			4									
<b>TEMPORARY PAVEMENT</b>																		
431+29.00 - 441+13.79	RT	TEMPORARY	984.79	VARIES	727.00	781.71							49.24					727.00
441+80.27 - 442+50.00	RT	TEMPORARY	69.73	VARIES	60.00	63.87							3.49					60.00
442+50.00 - 450+00.00	RT	TEMPORARY	750.00	VARIES	585.00	626.67							37.50					585.00
433+00.00 - 438+00.00	CT	TEMP. OVERLAY	500.00	26	585.00		452.00	125										
<b>TOTAL</b>						<b>2,045</b>	<b>285</b>	<b>452</b>	<b>347</b>	<b>4,492</b>	<b>58</b>	<b>7,580</b>	<b>648</b>	<b>90</b>	<b>124</b>	<b>2,928</b>	<b>7,738</b>	<b>1,372</b>

FILE NAME = P:\CBBEL\WEST Projects\2009\09-0147\_IL173\Civil\Ugn\Shk\0160129-int-schedule.dgn

**WILLS BURKE KELSEY ASSOCIATES LTD.**  
 116 West Main Street, Suite 201  
 St. Charles, Illinois 60174  
 (630) 443-7755

USER NAME = *USER*	DESIGNED - SBP/KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/6/2011	CHECKED - PJF	REVISED -
	DATE - 12/14/10	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE:	SHEET NO. 13 OF 106 SHEETS	STA.	TO STA.
--------	----------------------------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	132 B-2	MCHENRY	106	13
CONTRACT NO. 60129				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				