

PAVEMENT REMOVAL SCHEDULE

LOCATION	OFF.	REMARKS	AREA (SQ YD)	40600982	40600990	44000100	44000157	44000200	44004250	Z0004638	44201696	44201803	Z0004652
				HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	DRIVEWAY PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	PAVEMENT BREAKING	CLASS D PATCHES, TYPE IV, 4 INCH	CLASS D PATCHES, TYPE II, 13 INCH	APPROACH SLAB REMOVAL
ENTRANCES													
434+84.40	LT	HMA ENT.	62.0					122.4					
443+90.00	RT	HMA ENT.	184.0					58.4					
REMOVAL / BREAKING													
429+80.00 - 432+31.18		SURF. REM.	727.4				727.4						
432+31.18 - 436+63.06		REMOVAL	1246.1			1246.1				1392.1			
436+63.06 - 440+88.00		BREAKING	1392.1										
440+88.00 - 445+08.00		SLAB. REM.	59.0										59.0
441+83.00 - 442+05.00		SLAB. REM.	59.0										59.0
442+05.00 - 442+50.00		BREAKING	196.1							196.1			
442+50.00 - 445+09.08		BREAKING	989.2							989.2			
445+09.08 - 449+53.82		REMOVAL	1303.2			1303.2							
449+53.82 - 451+97.00		SURF. REM.	721.6				721.6						
432+30.00		PVT. BULKHEAD	11.6									11.6	
449+54.00		PVT. BULKHEAD	12.0									12.0	
437+87.00 - 440+88.00		SHEET PILING	67.0								67.0		
442+05.00 - 444+75.00		SHEET PILING	60.0								60.0		
429+80.00 - 429+86.50	LT	DRIVEWAY ACCESS	7.2		7.2								
429+80.00 - 429+86.50	RT	FINAL SURFACE	7.2		7.2								
451+97.00 - 451+90.50	RT	FINAL SURFACE	7.2		7.2								
451+97.00 - 451+90.50	RT	FINAL SURFACE	7.2		7.2								
432+31.00 - 436+63.06		TEMP. PAVEMENT	284.3			284.3							
436+63.06 - 440+54.00		TEMP. PAVEMENT	297.2							297.2			
440+54.00 - 441+13.00		TEMP. PAVEMENT	64.0			64.0							
441+80.00 - 442+03.00		TEMP. PAVEMENT	19.9			19.9							
442+03.00 - 445+09.00		TEMP. PAVEMENT	224.6							224.6			
445+09.00 - 449+53.80		TEMP. PAVEMENT	273.4			273.4							
431+41.60	LT	SHOULD-STAGE 3	59.7				59.7						
431+29.00	RT	TEMP. PVT.-STAGE 3	82.9				82.9						
449+53.82	LT	SHOULD-STAGE 3	64.3				64.3						
449+53.82	RT	TEMP. PVT.-STAGE 3	65.7				65.7						
431+29.00 - 441+13.79	RT	SOUTH EDGE OF EXISTING PAVEMENT (6")	54.7			54.7							
441+80.80 - 442+50.00	RT		3.8			3.8							
442+50.00 - 450+50.20	RT		44.5			44.5							
433+70.00 - 434+00.00	LT	STAGE 1C	43.3	43.3									
433+70.00 - 434+00.00	RT	STAGE 1C	63.3	63.3									
436+90.00 - 437+20.00	LT	STAGE 1C	43.3	43.3									
436+90.00 - 437+20.00	RT	STAGE 1C	63.3	63.3									
435+08.00 - 435+20.00	LT	STAGE 1C	15.1	15.1									
431+41.60 - 431+71.60	LT	STAGE 3	6.5	6.5									
431+41.60 - 431+71.60	RT	STAGE 3	6.5	6.5									
450+20.00 - 450+50.00	LT	STAGE 3	6.5	6.5									
450+20.00 - 450+50.00	RT	STAGE 3	6.5	6.5									
440+88.00 - 441+09.10	LT	EXST. SHOULDERS	14.4						14.4				
440+88.00 - 441+09.10	RT	EXST. SHOULDERS	17.8						17.8				
440+84.48 - 442+05.00	LT	EXST. SHOULDERS	14.6						14.6				
440+84.48 - 442+05.00	RT	EXST. SHOULDERS	17.0						17.0				
444+98.73 - 449+65.00	LT	EXST. SHOULDERS	182.0						182.0				
445+09.08 - 450+50.00	RT	EXST. SHOULDERS	141.0						141.0				
TOTAL				254	29	3,294	1,722	181	387	3,100	127	24	118

LANDSCAPING AND EROSION CONTROL SCHEDULE

LOCATION	OFF.	21101625	25000210	25000312	25100630	25100900	28000250	28000305	28000400	28100107	28200200	A2002920	A2006520	C2C01524
		TOPSOIL FURNISH AND PLACE, 6"	SEEDING, CLASS 2A	SEEDING, CLASS 4A	EROSION CONTROL BLANKET	TURF REINFORCE. MAT	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	STONE RIPRAP, CLASS A4	FILTER FABRIC	TREE (COMMON HACKBERRY), 2-1/2" CALIPER	TREE, (SWAMP WHITE OAK), 2-1/2" CALIPER	SHRUB (GREY DOGWOOD), 2' HEIGHT, CONTAINER
		(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(POUND)	(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(EACH)	(EACH)	(EACH)
429+80.00 - 435+77.00	LT	723.7	723.7			723.7	120	147	587					
429+80.00 - 435+71.40	RT	911.0	911.0			911.0	150	168	600					
435+75.00 - 441+25.00	LT	1033.8		1033.8		1,033.8	171	231	516	52	52			30
435+75.00 - 441+25.00	RT	1703.5		1703.5	469.2	1,234.3	282	231	535	73	73	5	5	30
441+25.00 - 442+00.00	LT	76.7		76.7	13.7	63.0	13	21	36	59	59			
441+25.00 - 442+00.00	RT	100.8		100.8	37.8	63.0	17	21	30	74	74			
442+00.00 - 444+64.70	LT	1077.2		1077.2	444.2	633.0	178	126	271					30
442+00.00 - 443+90.00	RT	1198.9	569.6	629.3	858.2	340.7	198	63	221					30
444+64.70 - 451+97.00	LT	1123.2	1123.2		822.2	301.0	186	21	709					
443+90.00 - 451+97.00	RT	2446.7	2446.7		967.4	1,479.3	405	273	882					
STAGE 1A														
434+84.00 - 435+39.00						44.44								
431+00.00 - 441+25.00	RT	1100.0			1,100.0		91	399						
441+25.00 - 450+50.00	RT	800.0			800.0	44.44	66	357						
MAINTENANCE / REPL.														
429+80.00 - 451+97.00	LT/RT							210	439					
TOTAL		12,296	5,774	4,621	5,513	6,872	1,877	2,268	4,826	258	258	5	5	120
		1.25 AC		1.00 AC										

FILE NAME = P:\CBBEL\MEST Project\2008\09-01\47_IL173\C:\v1\Draw\Sht\11660219-ht-schedule.dgn

WILLIS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = #USER#	DESIGNED - SBP/KMA	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 1/28/2011	CHECKED - PUF	REVISED -
	DATE - 1/25/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 14 OF 106 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	132 B-2	McHENRY	106	14
CONTRACT NO. 60129				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		