

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITIES	0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	13	13					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2501	2501					
25200110	SODDING, SALT TOLERANT	SO YD	13	13					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1918	1918					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	5	5					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	162	162					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	12649	12649					
40600300	AGGREGATE (PRIME COAT)	TON	108	108					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	583	583					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	41	41					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25746	25746					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2501	2501					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	272	272					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1918	1918					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1	1					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	162	162					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2265	2265					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	297	297					
42001300	PROTECTIVE COAT	SO YD	28	28					78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	26960	26960					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	281	281					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	5	5					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	356	356					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	54	54					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	62	62					
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	90	90					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1113	1113					
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	453	453					△ X5539700	STORM SEWERS TO BE CLEANED	FOOT	250	250					
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SO YD	6	6					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4					
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SO YD	10	10					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100					
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SO YD	47	47					△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	16	16					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	125	125					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1														
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2														
63200310	GUARDRAIL REMOVAL	FOOT	75	75														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5279	5279														
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	583	583														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25746	25746														

* SPECIALTY ITEMS
△ = Non-participating

FILE NAME =	USER NAME = poctech	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	143RD ST. (WILL COUNTY LINE TO IL RTE. 7 (WOLF RD.)) SUMMARY OF QUANTITIES	F.A.U. RTE. 1600	SECTION 2010-024 RS	COUNTY COOK	TOTAL SHEETS 22	SHEET NO. 3	
PLOT SCALE = 50,0000 "/ IN.		CHECKED -	REVISED -			SCALE: NONE	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			
PLOT DATE = 2/4/2011		DATE -	REVISED -			CONTRACT NO. 60K52					