SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	100	100					
25200110	SODDING, SALT TOLERANT	SQ YD	100	100					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46	46					
40600300	AGGREGATE (PRIME COAT)	TON	226	226					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	85	85					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	326	326					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5529	5529					
42001300	PROTECTIVE COAT	SQ YD	207	207					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	56419	56419					
44004250	PAVED SHOULDER REMOVAL	SQ YD	100	100					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	400	400					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	150	150					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	612	612					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	100	100					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					
60262700	INLETS TO BE RECONSTRUCTED	EACH	3	3					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	30	30					
60404950	FRAMES AND GRATES, TYPE 24	EACH	30	30					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15434	15434					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1462	1462					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24451	24451					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3845	3845					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	477	477					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	572	572					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5144	5144					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1462	1462					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24451	24451					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3845	3845					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	477	477					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	572	572					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	720	720					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	600	600					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	2747	2747					
	X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2328	2328					
Δ	X5539700	STORM SEWERS TO BE CLEANED	FOOT	2600	2600					
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20					
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1200	1200					
Δ	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	86	86					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

Δ = NON-PARTICIPATING
* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\banksl\d0211622\D152510-sht-plan.dgn	USER NAME = banksl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/20/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2706	126 RS-6	LAKE	24	3

CONTRACT NO. 60K56

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT