

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1 IL 25 TO MITCHELL RD. 0005	LOCATION 2 FARNSWORTH AVE. TO DUPAGE CO. LINE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1 IL 25 TO MITCHELL RD. 0005	LOCATION 2 FARNSWORTH AVE. TO DUPAGE CO. LINE 0005				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	24	12					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	878.8	696.8	182				
40600300	AGGREGATE (PRIME COAT)	TON	172	120	52					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38100	24800	13300				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	65	45	20					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3090	2300	790				
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	160	160					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	380	270	110					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1825	1350	475				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	475	185	290					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	380	300	80				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3615	2525	1090					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	510	345	165				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	42700	29800	12900					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	410	275	135				
44002232	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8"	SO YD	1050	410	640					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	925	925					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	648	240	408					X0325866	CENTER LINE - RUMBLE STRIP	FOOT	905		905				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	106	53	53					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	142	86	56				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	138	55	83					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1820	1275	545				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	575	350	225					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3					△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	2	2				
67100100	MOBILIZATION	L SUM	1	0.5	0.5					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	51.4	51.4				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5														
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5														
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4965	3590	1375														
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	878.8	696.8	182														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38100	24800	13300														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3090	2300	790														
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	160	160															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1825	1350	475														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	380	300	80														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1660	1200	460														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5														

△ = Non-participating