

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				EAST CRYSTAL LAKE AVENUE	
				80% FED 20% STATE	100% LOCAL
				ROADWAY 0004	WATERMAIN 0043
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	206	206	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	232	232	
20101000	TEMPORARY FENCE	FOOT	200	200	
20200100	EARTH EXCAVATION	CU YD	650	650	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	430	430	
20800150	TRENCH BACKFILL	CU YD	1,217	188	1,029
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,907	1,907	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	130	130	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24	24	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24	24	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24	24	
* 25100630	EROSION CONTROL BLANKET	SQ YD	1,907	1,907	
* 25200110	SODDING, SALT TOLERANT	SQ YD	1,907	1,907	
* 25200200	SUPPLEMENTAL WATERING	UNIT	92	92	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	394	394	
28000305	TEMPORARY DITCH CHECKS	FOOT	108	108	
28000400	PERIMETER EROSION BARRIER	FOOT	2,065	2,065	
28000510	INLET FILTERS	EACH	32	32	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	445	445	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1,375	1,375	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6	
40600300	AGGREGATE (PRIME COAT)	TON	30	30	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	210	210	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	261	261	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	30	6	24
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	600	600	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	70	70	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	400	400	
42001300	PROTECTIVE COAT	SQ YD	2,700	2,617	83
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	13,230	12,765	465
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	270	270	
42400800	DETECTABLE WARNINGS	SQ FT	96	96	

* SPECIALTY ITEMS

FILE NAME =	USER NAME = gellvanger	DESIGNED - GJE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EAST CRYSTAL LAKE AVENUE SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
F:\789-006 East Crystal Lake Ave SEGMENT	I:\CADD_Sheets\0163524-sht-500.dgn	DRAWN - GJE	REVISED -			116	06-00104-01-WR	McHENRY	64	3	
	PLOT SCALE = 20.0000' / IN.	CHECKED - JP	REVISED -			CONTRACT NO. 63524					
	PLOT DATE = 2/17/2011	DATE - 02/7/2011	REVISED -			SCALE: NONE	SHEET NO. 3 OF 64 SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT