

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				EAST CRYSTAL LAKE AVENUE	
				80% FED 20% STATE ROADWAY 0004	100% LOCAL WATERMAIN 0043
* A2008316	TREE, TILIA TOMENTOSA (SILVER LINDEN), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	
* B0001716	TREE, AMELANCHIER X GRANDIFLORA APPLE, (APPLE SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	
* D2001572	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 6' HEIGHT, BALLED AND BURLAPPED	EACH	2	2	
* D2002288	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	1	1	
* X0323353	GATE VALVES, 10"	EACH	2		2
* X5610656	WATER MAIN TO BE ABANDONED, 6"	FOOT	1,268		1,268
* X5610658	WATER MAIN TO BE ABANDONED, 8"	FOOT	20		20
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	23	23	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2	
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3,200	3,200	
X5539700	STORM SEWERS TO BE CLEANED	FOOT	150	150	
* X5630006	CUT AND CAP EXISTING 6" WATER MAIN	EACH	6		6
* X5630008	CUT AND CAP EXISTING 8" WATER MAIN	EACH	2		2
* X5630710	CONNECTION TO EXISTING WATER MAIN 10"	EACH	1		1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* XX006111	WATER SERVICE RECONNECTION, WITH NEW BUFFALO BOX, LONG SIDE 1" (MINIMUM)	EACH	11		11
* XX006112	WATER SERVICE RECONNECTION, WITH NEW BUFFALO BOX, SHORT SIDE 1" (MINIMUM)	EACH	16		16
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2,200	2,200	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	604	604	
Z0062456	TEMPORARY PAVEMENT	SQ YD	90	90	
Z0076600	TRAINEES	HOUR	1,000	1,000	△

\* SPECIALTY ITEMS

△ CONSTRUCTION TYPE - CODE 0042

Total Estimated Cost

FILE NAME = F:\789-006 East Crystal Lake Ave SEGMENT	USER NAME = gellwanger	DESIGNED - GJE	REVISED - GJE 3/9/2011	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EAST CRYSTAL LAKE AVENUE SUMMARY OF QUANTITIES</b>			F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	INCADD_Sheets\DI63524-sht-500.dgn	DRAWN - GJE	REVISED -		116	06-00104-01-WR	McHENRY	64	6			
	PLOT SCALE = 20.0000' / IN.	CHECKED - JP	REVISED -		SCALE: NONE			SHEET NO. 6 OF 64 SHEETS		STA.	TO STA.	
	PLOT DATE = 3/9/2011	DATE - 02/1/2011	REVISED -		ILLINOIS FED. AID PROJECT CONTRACT NO. 63524							