

| PROPOSED ROADWAY PAVEMENT | | | | | | | |
|---------------------------|-----------------------------------|------------------------------|-----------------------------|---|---------------------------------------|----------------------------------|--|
| LOCATION STATION-STATION | BIT. MATERIALS (PRIME COAT) (TON) | AGGREGATE (PRIME COAT) (TON) | HMA BASE COURSE, 8" (SQ YD) | LEVELING BINDER (MACHINE METHOD), N70 (TON) | HMA BINDER COURSE, IL-19.0, N70 (TON) | AGGREGATE SUBGRADE, 12" (SQ. YD) | HMA SURFACE COURSE, MIX "D", N70 (TON) |
| EAST CRYSTAL LAKE AVE | | | | | | | |
| 122+00 - 128+00 | 1.275 | 6.375 | 305.04 | 45.84 | 136.32 | 4673.04 | 90.72 |
| 128+00 - 134+00 | 2.64 | 13.2 | 631.69 | 95.5 | 278.32 | 9735.5 | 185.22 |
| 134+00 - 140+00 | 1.395 | 6.975 | 334.27 | 49.66 | 147.68 | 5062.46 | 98.28 |
| EAST STREET | 0.015 | 0.765 | - | 5.5 | 16 | - | 11 |
| MORGAN STREET | 0.015 | 0.753 | - | 5.5 | 16 | - | 11 |
| TOTAL | 6 | 30 | 1280 | 210 | 600 | 2200 | 400 |

| DRIVEWAY REPLACEMENT | | | | | | |
|----------------------|-----------------------|--------|--------------|--------------------------------|----------------------|----------------------|
| NO. | STATION | OFFSET | AREA (SQ YD) | HMA SURFACE MIX "C", N50 (TON) | HMA BASE, 6" (SQ YD) | HMA BASE, 8" (SQ YD) |
| 1 | 125+81.35 CE | RT | 66.70 | 7.47 | - | 66.70 |
| 2 | 127+32.22 | LT | 19.49 | 2.18 | 19.49 | - |
| 3 | 127+88.96 | LT | 15.08 | 1.69 | 15.08 | - |
| 4 | 127+93.03 | RT | 17.64 | 1.98 | 17.64 | - |
| 5 | 128+0.952 | LT | 16.13 | 1.81 | 16.13 | - |
| 6 | 128+71.79 | LT | 13.41 | 1.50 | 13.41 | - |
| 7 | 129+34.65 | RT | 12.78 | 1.43 | 12.78 | - |
| 8 | 129+38.3 | LT | 13.51 | 1.51 | 13.51 | - |
| 9 | 130+1.8 | LT | 15.58 | 1.74 | 15.58 | - |
| 10 | 130+03.59 | RT | 11.80 | 1.32 | 11.80 | - |
| 11 | 131+13.39 | LT | 17.06 | 1.91 | 17.06 | - |
| 12 | 131+46.37 | RT | 55.75 | 6.24 | 55.75 | - |
| 13 | 132+38.76 | RT | 13.88 | 1.55 | 13.88 | - |
| 14 | 132+95.8 | RT | 35.56 | 3.98 | 35.56 | - |
| 15 | 133+65.15 | LT | 12.34 | 1.38 | 12.34 | - |
| 16 | 133+85.9 | RT | 12.97 | 1.45 | 12.97 | - |
| 17 | 134+42.22 | LT | 7.72 | 0.86 | 7.72 | - |
| 18 | 134+61.24 | LT | 7.08 | 0.79 | 7.08 | - |
| 19 | 134+41.14 CE | RT | 26.31 | 2.95 | - | 26.31 |
| 20 | 134+79.11 | RT | 26.97 | 3.02 | 26.97 | - |
| 21 | 135+98.47 & 136+38.25 | RT | 91.57 | 10.26 | 91.57 | - |
| 22 | 136.05.01 | LT | 8.14 | 0.91 | 8.14 | - |
| 23 | 136+94.56 | LT | 7.58 | 0.85 | 7.58 | - |
| TOTAL | | | 525 | 70 | 445 | 95 |

| TEMPORARY PAVEMENT | |
|-----------------------|-------------------|
| STAGE | QUANTITY (SQ. YD) |
| EAST CRYSTAL LAKE AVE | |
| STAGE 1 | 24.44 |
| STAGE 2 | 26.9 |
| STAGE 3 | 32.67 |
| TOTAL | 90 |

| CONCRETE MEDIAN | |
|-----------------------|------|
| LOCATION STA. - STA. | TYPE |
| EAST CRYSTAL LAKE AVE | |
| 125+10 - 127+4.5 | 1554 |
| TOTAL | 1554 |

| TEMPORARY PAVEMENT MARKING | | | | | |
|----------------------------|----------------------|-----------|---------|----------|---------------------------|
| STAGE | LOCATION STA. - STA. | LINE SIZE | | | LETTERS & SYMBOLS (SQ FT) |
| | | 4" (FT) | 6" (FT) | 24" (FT) | |
| EAST CRYSTAL LAKE AVE | | | | | |
| STAGE 1 | 125+10 - 128+00 | 662.95 | 76.1 | 121.2 | 122.4 |
| | 128+00 - 134+00 | 1381.15 | 49.6 | 14 | - |
| | 134+00 - 137+17 | 18.3 | - | - | - |
| | TOTAL | 2762.3 | 125.7 | 135.2 | 122.4 |
| EAST CRYSTAL LAKE AVE | | | | | |
| STAGE 2 | 125+10 - 128+00 | 764.88 | 76.1 | 122.4 | 122.4 |
| | 128+00 - 134+00 | 1593.5 | 49.6 | 10 | - |
| | 134+00 - 137+17 | 828.62 | - | - | - |
| | TOTAL | 3187 | 125.7 | 132.4 | 122.4 |
| EAST CRYSTAL LAKE AVE | | | | | |
| STAGE 3 | 125+10 - 128+00 | 709.68 | 88.7 | 99.2 | 122.4 |
| | 128+00 - 134+00 | 1478.5 | 82.2 | 17.2 | - |
| | 134+00 - 137+17 | 768.82 | - | - | - |
| | TOTAL | 2957 | 170.9 | 116.4 | 122.4 |
| | GRAND TOTAL | 8906 | 422 | 400 | 370 |

| COMBINATION CONCRETE CURB & GUTTER | | | |
|------------------------------------|-------------|-------------|-------------|
| LOCATION STA. - STA. | TYPE | | |
| | B-6.12 (FT) | B-6.24 (FT) | M-6.24 (FT) |
| EAST CRYSTAL LAKE AVE | | | |
| 125+10 - 128+00 | 314 | 535 | 75 |
| 128+00 - 134+00 | - | 1415 | - |
| 134+00 - 137+17 | - | 1000 | - |
| TOTAL | 314 | 2950 | 75 |

| PROPOSED PAVEMENT MARKING | | | | | | |
|---------------------------|---------------|---------|----------|----------|---------------------------|-------------------------------|
| LOCATION STA. - STA. | THERMOPLASTIC | | | | LETTERS & SYMBOLS (SQ FT) | RAISED REFLEC. MARKERS (EACH) |
| | MARKING LINE | | | | | |
| | 4" (FT) | 6" (FT) | 12" (FT) | 24" (FT) | | |
| EAST CRYSTAL LAKE AVE | | | | | | |
| 125+10 - 128+00 | 750 | 88.9 | 6 | 92.7 | 122.2 | 4 |
| 128+00 - 134+00 | 1620 | 89.4 | - | 16.5 | 124.8 | 28 |
| 134+00 - 137+17 | 1309.27 | 115 | 44.6 | - | 67.6 | 20 |
| TOTAL | 3700 | 300 | 55 | 110 | 320 | 52 |

| PAVEMENT MARKING TAPE, TYPE III | | | | |
|---------------------------------|----------------------|-----------|----------|---------------------------|
| STAGE | LOCATION STA. - STA. | LINE SIZE | | |
| | | 4" (FT) | 24" (FT) | LETTERS & SYMBOLS (SQ FT) |
| EAST CRYSTAL LAKE AVE | | | | |
| STAGE 1 | 125+10 - 128+00 | 426.28 | 28 | 61.2 |
| | 128+00 - 134+00 | - | - | - |
| | 134+00 - 137+17 | 789.08 | - | - |
| | TOTAL | 1215.36 | 28 | 61.2 |
| EAST CRYSTAL LAKE AVE | | | | |
| STAGE 2 | 125+10 - 128+00 | 445.57 | 28 | 61.2 |
| | 128+00 - 134+00 | - | - | - |
| | 134+00 - 137+17 | 363.84 | - | - |
| | TOTAL | 809.41 | 28 | 61.2 |
| EAST CRYSTAL LAKE AVE | | | | |
| STAGE 3 | 125+10 - 128+00 | 709.68 | 99.2 | 122.4 |
| | 128+00 - 134+00 | 1478.5 | 17.2 | - |
| | 134+00 - 137+17 | 768.82 | - | - |
| | TOTAL | 2957 | 116.4 | 122.4 |
| | GRAND TOTAL | 5000 | 190 | 250 |

| 5" PCC SIDEWALK 5' WIDE | | | |
|-------------------------|----------------------|--------|------------------|
| NO. | LOCATION STA. - STA. | OFFSET | QUANTITY (SQ FT) |
| EAST CRYSTAL LAKE AVE | | | |
| 1 | 125+10 - 128+00 | LT | 1174.4 |
| 2 | 125+10 - 128+00 | RT | 970.1 |
| 3 | 128+00 - 134+00 | LT | 1070.4 |
| 4 | 128+00 - 134+00 | RT | 1825.1 |
| | TOTAL | | 5040 |

| 8" PCC SIDEWALK 6' WIDE | | | |
|-------------------------|----------------------|--------|------------------|
| NO. | LOCATION STA. - STA. | OFFSET | QUANTITY (SQ FT) |
| EAST CRYSTAL LAKE AVE | | | |
| 1 | 131+34 - 131+77 | RT | 270 |
| | TOTAL | | 270 |

| 5" PCC SIDEWALK 7' WIDE | | | |
|-------------------------|----------------------|--------|------------------|
| NO. | LOCATION STA. - STA. | OFFSET | QUANTITY (SQ FT) |
| EAST CRYSTAL LAKE AVE | | | |
| 1 | 128+00 - 134+00 | LT | 1433.3 |
| 2 | 128+00 - 134+00 | RT | 1778.2 |
| 3 | 134+00 - 137+17 | LT | 2759.2 |
| 4 | 134+00 - 137+17 | RT | 2219.3 |
| | TOTAL | | 8190 |

NOTE: PERSONAL SIDEWALKS WILL BE REPLACED UP TO THE R.O.W. THESE QUANTITIES ARE INCLUDED IN THE ABOVE SCHEDULE.

NOTE: BASIS OF MEASUREMENT AND PAYMENT PER STANDARD SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, AND RECURRING SPECIAL PROVISIONS UNLESS MARKED IN THE MARGIN WITH "SPL" WHICH IDENTIFIES THOSE ITEMS WHICH ARE RULED BY SECTIONS OF THE CONTRACT SPECIAL PROVISIONS.