

**SUMMARY OF QUANTITIES (CONT.)**

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NUMBER	DESCRIPTION	UNITS		BRIDGE 0011	NON-PARTICIPATING
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	0
67100100	MOBILIZATION	L SUM	1	1	0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	0
70106700	TEMPORARY RUMBLE STRIPS	EACH	12	12	0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16	0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,480	1,480	0
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	15,870	15,870	0
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,009	1,009	0
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	240	240	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	916	916	0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	605	605	0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	535	535	0
* 72000100	SIGN PANEL - TYPE 1	SQ FT	52	52	0
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9	9	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,517	2,103	1,414
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	15	0	15
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	501	501	0
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8	0
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	0
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	19	19	0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	586	586	0
* A2007820	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3	0
* B2000120	TREE, ACER CAMPESTRE (HEDGE MAPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	3	0
* B2001620	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2-1/2" CALIPER TREE FORM, BALLED AND BURLAPPED	EACH	3	3	0
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2,930	2,930	0
Z0004552	APPROACH SLAB REMOVAL	SQ YD	208	208	0
* Z0007124	STEEL RAILING (SPECIAL)	FOOT	249	249	0
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0
Z0019600	DUST CONTROL WATERING	UNIT	42	42	0
Z0022800	FENCE REMOVAL	FOOT	495	495	0
Z0026407	TEMPORARY SHEET PILING	SQ FT	1,624	1,624	0

• DENOTES SPECIAL ITEMS  
 Δ CONSTRUCTION CODE 0042

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NUMBER	DESCRIPTION	UNITS		BRIDGE 0011	NON-PARTICIPATING
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	0
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	0
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	551	551	0
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	170	170	0
Z0066600	STABILIZED DRIVEWAYS 8"	SQ YD	160	160	0
Δ Z0076600	TRAINEES	hour	1,000	1,000	0
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	13	0	13
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	188	188	0
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2	0
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	2	0
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	91	0	91
* X6310088	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	EACH	4	4	0
X7010202	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1	0
* X7280105	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	FOOT	93	93	0
* X7310110	BASE FOR TELESCOPING SIGN SUPPORT, SPECIAL	EACH	5	5	0
* X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	41	26	15
XX006922	RUMBLE STRIP REMOVAL	EACH	12	12	0

• DENOTES SPECIAL ITEMS  
 Δ CONSTRUCTION CODE 0042

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. 184-001227 EXP. 12/31/2011  
 2/16/2011 10:28:18 AM



DESIGNED - CAC	REVISED - PER IDOT 10-25-10
DRAWN - BCD	REVISED - PER IDOT 02-14-11
CHECKED - MDW	REVISED -
DATE - 08/20/10	FILE - 070630-S0002.sh+

**MCHENRY COUNTY DIVISION OF TRANSPORTATION  
 LAWRENCE ROAD BRIDGE OVER  
 LAWRENCE CREEK**

**SUMMARY OF QUANTITIES**

SCALE: NONE STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0028	06-00320-01-BR	MCHENRY	70	5
JOB NO. C-91-139-11 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63535 BRS-0028107	