

MCHENRY COUNTY
DIVISION OF TRANSPORTATION

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back S. Abut.	106+55.75	2.67	896.24	896.24
☉ S. Abut.	106+57.00	2.67	896.23	896.23
A	106+67.00	2.67	896.18	896.21
B	106+77.00	2.67	896.13	896.19
C	106+87.00	2.67	896.08	896.16
D	106+97.00	2.67	896.03	896.13
E	107+07.00	2.67	895.98	896.08
F	107+17.00	2.67	895.93	896.02
G	107+27.00	2.67	895.88	895.95
H	107+37.00	2.67	895.83	895.87
☉ N. Abut.	107+49.00	2.67	895.77	895.77
Back N. Abut.	107+50.25	2.67	895.76	895.76

STAGE CONSTRUCTION LINE

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back S. Abut.	106+55.75	5.83	896.17	896.17
☉ S. Abut.	106+57.00	5.83	896.16	896.16
A	106+67.00	5.83	896.11	896.15
B	106+77.00	5.83	896.06	896.13
C	106+87.00	5.83	896.01	896.10
D	106+97.00	5.83	895.96	896.06
E	107+07.00	5.83	895.91	896.01
F	107+17.00	5.83	895.86	895.95
G	107+27.00	5.83	895.81	895.89
H	107+37.00	5.83	895.76	895.80
☉ N. Abut.	107+49.00	5.83	895.70	895.70
Back N. Abut.	107+50.25	5.83	895.70	895.70

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back S. Abut.	106+55.75	8.00	896.12	896.12
☉ S. Abut.	106+57.00	8.00	896.12	896.12
A	106+67.00	8.00	896.07	896.10
B	106+77.00	8.00	896.02	896.08
C	106+87.00	8.00	895.97	896.05
D	106+97.00	8.00	895.92	896.02
E	107+07.00	8.00	895.87	895.97
F	107+17.00	8.00	895.82	895.91
G	107+27.00	8.00	895.77	895.84
H	107+37.00	8.00	895.72	895.76
☉ N. Abut.	107+49.00	8.00	895.66	895.66
Back N. Abut.	107+50.25	8.00	895.65	895.65

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back S. Abut.	106+55.75	13.33	896.01	896.01
☉ S. Abut.	106+57.00	13.33	896.01	896.01
A	106+67.00	13.33	895.96	895.99
B	106+77.00	13.33	895.91	895.97
C	106+87.00	13.33	895.86	895.94
D	106+97.00	13.33	895.81	895.90
E	107+07.00	13.33	895.76	895.86
F	107+17.00	13.33	895.71	895.79
G	107+27.00	13.33	895.66	895.73
H	107+37.00	13.33	895.61	895.65
☉ N. Abut.	107+49.00	13.33	895.55	895.55
Back N. Abut.	107+50.25	13.33	895.54	895.54

BEAM 8

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back S. Abut.	106+55.75	18.67	895.90	895.90
☉ S. Abut.	106+57.00	18.67	895.90	895.90
A	106+67.00	18.67	895.85	895.88
B	106+77.00	18.67	895.80	895.86
C	106+87.00	18.67	895.75	895.83
D	106+97.00	18.67	895.70	895.79
E	107+07.00	18.67	895.65	895.75
F	107+17.00	18.67	895.60	895.68
G	107+27.00	18.67	895.55	895.62
H	107+37.00	18.67	895.50	895.54
☉ N. Abut.	107+49.00	18.67	895.44	895.44
Back N. Abut.	107+50.25	18.67	895.43	895.43

DESIGNED <i>BLB</i>
CHECKED <i>AS</i>
DRAWN <i>BCD</i>
CHECKED <i>BLB</i>

**TOP OF SLAB ELEVATIONS
STRUCTURE NO. 056-3181**

SHEET NO. 7 25 SHEETS	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	0028	06-00320-01-BR	MCHENRY	70	31
CONTRACT NO. 63535					
JOB NO. C-91-139-11 ILLINOIS FED. AID PROJECT BRS-0028(107)					

COPYRIGHT © 2008 BY BAYNE & WOODMAN, INC. ...
 ILLINOIS PROFESSIONAL ENGINEERING LICENSE NO. 184-001875 EXPIRES 4/30/2011
 ILLINOIS PROFESSIONAL SURVEYING LICENSE NO. 070630-01 EXPIRES 2/28/2011
 ILLINOIS PROFESSIONAL LAND SURVEYING LICENSE NO. 070630-01 EXPIRES 2/28/2011