

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY					
					ROADWAY	71st STREET BRIDGE SN 016-7721	RETAINING WALLS SN 016-7722 THRU SN016-7726	TRAINES	71st STREET PUMPING STATION
					0004	0008	0040	0042	0043
	44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	665	665				
	44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	171	171				
	50105220	PIPE CULVERT REMOVAL	FOOT	38	38				
	50200100	STRUCTURE EXCAVATION	CU YD	2,398	0	2,398			
	50300225	CONCRETE STRUCTURES	CU YD	2,392	0	1,182.1	1,209.9		
	50300285	FORM LINER TEXTURED SURFACE	SQ FT	28,800	0	2,111	26,689		
	50300300	PROTECTIVE COAT	SQ YD	1,974	0	1,974			
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	0	1			
	50500505	STUD SHEAR CONNECTORS	EACH	8,521	0		8,521		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	279,522	62	154,530	124,930		
	50800515	BAR SPLICERS	EACH	320	0	320			
*	50900105	ALUMINUM RAILING, TYPE L	FOOT	1,700	0		1,700		
	51500100	NAME PLATES	EACH	1		1			
	52100400	STEEL BEARING ASSEMBLY	EACH	19	0	19			
	52100530	ANCHOR BOLTS, 1 1/4"	EACH	76	0	76			
	52100540	ANCHOR BOLTS, 1 1/2"	EACH	38	0	38			
	542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	5	5				
	54210562	PIPE ELBOW, 78"	EACH	2	2				
	54210568	PIPE ELBOW, 84"	EACH	6	6				
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
	54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1				
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	173	173				
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,824	1,824				
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	815	815				
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	83	83				
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	244	244				
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	111	111				
	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	279	279				
	550A0530	STORM SEWERS, CLASS A, TYPE 2 78"	FOOT	84	84				
	550A0540	STORM SEWERS, CLASS A, TYPE 2 84"	FOOT	886	886				
	550A0730	STORM SEWERS, CLASS A, TYPE 3 30"	FOOT	261	261				
	550A0770	STORM SEWERS, CLASS A, TYPE 3 42"	FOOT	74	74				
	550A1620	STORM SEWERS, CLASS A, TYPE 6 36"	FOOT	259	259				
	55100500	STORM SEWER REMOVAL 12"	FOOT	1,108	1,108				
	55100700	STORM SEWER REMOVAL 15"	FOOT	262	262				
	55101200	STORM SEWER REMOVAL 24"	FOOT	510	510				
	55102400	STORM SEWER REMOVAL 78"	FOOT	168	168				
	55102500	STORM SEWER REMOVAL 84"	FOOT	1,073	1,073				
*	56100700	WATER SERVICE MAIN 8"	FOOT	50	50				

* DENOTES SPECIALTY ITEM

FILE NAME = P:\63555677\020_040_001_Drawing\Sheet\Sheet\016\016155877-int-500-02.dgn



USER NAME = manuj
 PLOT SCALE = 1/800" = 1" / in.
 PLOT DATE = 3/16/2011

DESIGNED - NJH
 DRAWN - NJH
 CHECKED - TJW
 DATE - March 17, 2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1537	06-00050-00-GS	COOK	209	5
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT CRE-9003(709)			CONTRACT NO. 63556	