

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
CONSTRUCTION CODE - 0021			
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1269
* 42400800	DETECTABLE WARNINGS	SQ FT	161
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	140
* 44000600	SIDEWALK REMOVAL	SQ FT	1174
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	140
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	30
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	114
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	451
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	502
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	32
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	61
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	25
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	146
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	316
81400100	HANDHOLE	EACH	4
81400200	HEAVY-DUTY HANDHOLE	EACH	2
81400300	DOUBLE HANDHOLE	EACH	2
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	706
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1086
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1402
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1626
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	649
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1457
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	34

CODE NO.	ITEM	UNIT	TOTAL
CONSTRUCTION CODE - 0021			
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	30
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	3
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10
88500100	INDUCTIVE LOOP DETECTOR	EACH	8
88600100	DETECTOR LOOP, TYPE I	FOOT	734
88700200	LIGHT DETECTOR	EACH	2
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
89502380	REMOVE EXISTING HANDHOLE	EACH	8
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	260
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1
81200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	1
87301900	Electric Cable in Conduit, Equipment Grounding Conductor, No. 6 1 C	FOOT	545

* SPECIALTY ITEM

PROFILE SURVEYED PLOTTED CHECKED
 NOTE BOOK PLAN, NOTED
 STRUCTURE NOTATIONS CHFD
 NO. _____
 BY _____ DATE _____
 SURVEYED PLOTTED CHECKED
 NOTE BOOK PLAN, NOTED
 CAD FILE NAME
 NO. _____
 BY _____ DATE _____

CHRISTOPHER B. BURKE ENGINEERING LTD.
 9575 West Higgins Road, Suite 600
 Rosemont, Illinois 60018
 (847) 823-0500