

# SUMMARY OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	100% State 0014 QUANTITY
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	69.5
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	705.8
50102400	CONCRETE REMOVAL	CU YD	24.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	24.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,680
50800515	BAR SPLICERS	EACH	22
52000110	PREFORMED JOINT STRIP SEAL	FOOT	83
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	705.8
67100100	MOBILIZATION	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	285
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,463
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	873

PAY ITEM #	DESCRIPTION	UNIT	100% State 0014 QUANTITY
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	36
70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,425
78300100	PAVEMENT MARKING REMOVAL	SQ FT	280
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	180
<del>XZ030256</del>	<del>IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE, NARROW), TEST LEVEL 3</del>	<del>EACH</del>	<del>2</del>
<del>XZ030260</del>	<del>IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3</del>	<del>EACH</del>	<del>2</del>
X5030530	FLOOR DRAIN EXTENSION	EACH	24
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	125
Z0015802	PLUG EXISTING DECK DRAINS	EACH	42
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
X5080600	MECHANICAL SPLICERS	EACH	10

\*specialty items

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES Structure No. 043-0035</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
D:\BR\CADD plans\Jo Davless County\0430035\PLANeng.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -			301	(298-1)M-1	Jo Davless	16	2	
PLOT DATE = Wed Dec 28 10:57:40 2010	DATE -	CHECKED -	REVISED -			CONTRACT NO. G4G81					
						ILLINOIS FED. AID PROJECT					