SUMMARY OF QUANTITIES

PAY ITEM	DESCRIPTION	UNIT	100 % State 0014
50102400	CONCRETE REMOVAL	CU YD	5.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	5.9
50300300	PROTECTIVE COAT	SQ YD	26.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	680
50800515	BAR SPLICERS	EACH	6
52000110	PREFORMED JOINT STRIP SEAL	FOOT	120
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,176.5
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	750
70400100	TEMPORARY CONCRETE BARRIER	FOOT	762.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	725
X7010218	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	20
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	23
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	98
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1