SUMMARY OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	100% State 0014 QUANTITY
50102400	CONCRETE REMOVAL	CU YD	30.2
50300100	FLOOR DRAINS	EACH	6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	30.2
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	684
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,880
~~58300100~~	~~PORTLAND CEMENT MORTAR FAIRING COURSE~~	~~FOOT~~	~~228~~
67100100	MOBILIZATION	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,113
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	420
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24
70400100	TEMPORARY CONCRETE BARRIER	FOOT	287.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	287.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,425
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	684
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	3
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

* Specialty Items

FILE NAME = O:\BR\CADD plans\Jo Daviess County\0430040\PLANeng.dgn	USER NAME = linkdj	DESIGNED - ---	REVISED - --- ---------
		DRAWN - ---	REVISED - --- ---------
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - ---	REVISED - --- ---------
	PLOT DATE = Fri Jan 28 08:09:20 2011	DATE - --------	REVISED - --- ---------

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Summary of Quantities

SCALE: _____ | SHEET NO. __ OF ___ SHEETS | STA. _____ TO STA. _____

Rev.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	(10BR-3)M	JODAVIESS	12	3

CONTRACT NO. 64G90

ILLINOIS FED. AID PROJECT