

90% FED. / 10% STATE

ROADWAY

I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)
I-57 OVER (S&B)

ILLINOIS CENTRAL RR
BY BRADLEY

SIGNALS
(BY 100%)
BY BRADLEY

SAFETY
(BY 100%)
BY BRADLEY

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0004	0011	0011	0021	0021
40600300	AGGREGATE (PRIME COAT)	TON	5	5				
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	257	257				
40600895	CONSTRUCTING TEST STRIP	EACH	6	6				
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	7,040	7,040				
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	5,239	5,239				
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1,012	1,012				
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	5,864	5,864				
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	2,199	2,199				
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	2,454	2,454				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	304					304
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	42,331	42,331				
42001200	PAVEMENT FABRIC	SQ YD	42,331	42,331				
42001300	PROTECTIVE COAT	SQ YD	139,215	139,215				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2,726	2,726				
42100345	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12 1/4"	SQ YD	52,712	52,712				
42100615	PAVEMENT REINFORCEMENT	SQ YD	52,712	52,712				
42101030	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 36'	EACH	2	2				
42101100	TRANSVERSE TERMINAL JOINT COMPLETE 36'	EACH	4	4				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	332					332
42400800	DETECTABLE WARNINGS	SQ FT	80					80
44000100	PAVEMENT REMOVAL	SQ YD	80,387	80,387				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	31,165	31,165				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	5,832	5,832				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	141	141				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,541	6,541				
44003100	MEDIAN REMOVAL	SQ FT	35,148	35,148				
44004000	PAVED DITCH REMOVAL	FOOT	1,144.1	1,144.1				
44004250	PAVED SHOULDER REMOVAL	SQ YD	62,660	62,660				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	81	81				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	22	22				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	125	125				
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	38	38				
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	32	32				
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SQ YD	27	27				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	950	950				

• DENOTES SPECIALTY ITEM

FILE NAME = I:\Dgn\sheets\sq02.dgn	USER NAME = EJG	DESIGNED - JWM DRAWN - JWM CHECKED - EJG PLOT DATE = 12/22/2010	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION (46-2) I, HBR, VBR	COUNTY KANKAKEE	TOTAL SHEETS 558	SHEET NO. 5
				SCALE: NONE SHEET NO. 2 OF 11 SHEETS STA. TO STA.			CONTRACT NO. 66409					
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT												