

90% FED. / 10% STATE
 ROADWAY
 SN 046-0015 (MB)
 I-57 OVER CSB
 SN 046-0016 (MB)
 ILLINOIS CENTER RR
 SN 046-0017 (MB)
 I-57 OVER SIGNAL RR
 BY BRADLEY
 SIGNALS
 BY BRADLEY
 SAFETY
 BY BRADLEY

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0004	0011	0011	0021	0021
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	497.8	497.8				
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	60.8	60.8				
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	330.9	330.9				
542A8215	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	128.5	128.5				
542A8221	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 36"	FOOT	184.0	184.0				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	13	13				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	5	5				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	16	16				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	6	6				
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2				
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	4	4				
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	6	6				
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	2	2				
54248160	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36"	EACH	4	4				
54248510	CONCRETE COLLAR	CU YD	4.4	4.4				
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	48.1	48.1				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,152.8	1,152.8				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3,550.0	3,550.0				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1,710.8	1,710.8				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,125.4	1,125.4				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,060.9	1,060.9				
550A5300	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 36"	FOOT	246.2	246.2				
55100500	STORM SEWER REMOVAL 12"	FOOT	939.3	939.3				
55100700	STORM SEWER REMOVAL 15"	FOOT	307.8	307.8				
55100900	STORM SEWER REMOVAL 18"	FOOT	301.4	301.4				
55101200	STORM SEWER REMOVAL 24"	FOOT	652.1	652.1				
55101400	STORM SEWER REMOVAL 30"	FOOT	195.8	195.8				
55101600	STORM SEWER REMOVAL 36"	FOOT	452.0	452.0				
58700300	CONCRETE SEALER	SQ FT	9,149		9,149			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	555	112	203	240		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	38	38				
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	19	19				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11				

• DENOTES SPECIALTY ITEM

FILE NAME =
 I:\Dgn\sheets\sq024.dgn

USER NAME = EriG
 PLOT SCALE = 1/50
 PLOT DATE = 12/22/2010

DESIGNED - JWM
 DRAWN - JWM
 CHECKED - EJC
 DATE - 12/17/10

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 11 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(46-2) I, HBR, VBR	KANKAKEE	558	7
CONTRACT NO. 66409				

FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT