CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				90% FED / 10% STATE				
				ROADWAY	I-57 OVER IL ROUTE 50 SN 046-0014 (SB) SN 046-0015 (NB)	I-57 OVER ILLINOIS CENTRAL RR SN 046-0016 (SB) SN 046-0017 (NB)	SIGNALS (PAID 100% BY BRADLEY)	SAFETY (PAID 100% BY BRADLEY)
				URBAN				
				0004	0011	0011	0021	0021
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	5	5				
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	7	7				
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	8	8				
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	3	3				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6				
60255500	MANHOLES TO BE ADJUSTED	EACH	9	9				
60270050	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAME AND GRATES	EACH	34	34				
60500040	REMOVING MANHOLES	EACH	1	1				
60500050	REMOVING CATCH BASINS	EACH	7	7				
60500205	FILLING CATCH BASINS	EACH	11	11				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	35.0	35.0				
60600605	CONCRETE CURB, TYPE B	FOOT	66					66
60602800	CONCRETE GUTTER, TYPE B	FOOT	166	166				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	11,490	11,490				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	47,694	47,694				
• 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2,125.0	2,125.0				
• 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2				
• 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1				
• 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6				
• 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7				
63200310	GUARDRAIL REMOVAL	FOOT	9,317	9,317				
63500105	DELINEATORS	EACH	786	786				
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	6,913	6,913				
63700805	CONCRETE BARRIER TRANSITION	FOOT	60	60				
63700900	CONCRETE BARRIER BASE	FOOT	6,973	6,973				
63801100	MODULAR BLADE-TYPE GLARE SCREENS	FOOT	19,175	19,175				
64200105	SHOULDER RUMBLE STRIPS	FOOT	24,876	24,876				
66400105	CHAIN LINK FENCE, 4'	FOOT	2,736	2,736				
66500105	WOVEN WIRE FENCE, 4'	FOOT	12,678	12,678				
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3				
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	40	40				
67100100	MOBILIZATION	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	140	140				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	88,414	88,414				

• DENOTES SPECIALTY ITEM

Rev.

FILE NAME = I:\Dgn\sheets\sq005.dgn	USER NAME = EricG	DESIGNED - JWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN - JWM	REVISED -			57	(46-2) I, HBR, VBR	KANKAKEE	558 / 8
	PLOT SCALE = 1:50	CHECKED - EJG	REVISED -					CONTRACT NO. 66409	
	PLOT DATE = 12/22/2010	DATE - 12/17/10	REVISED -		SCALE: NONE / SHEET NO. 5 OF 11 SHEETS / STA. / TO STA.	FED. ROAD DIST. NO. 3	ILLINOIS	FED. AID PROJECT	