

90% FED/10% STATE
 ROADWAY
 URBAN
 I-57 OVER SR 046-0015 (WB)
 I-57 OVER SR 046-0017 (WB)
 ILLINOIS CENTRAL RR BY BRADLEY
 SIGNALS (BY BRADLEY)
 SAFETY (BY BRADLEY)

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0004	0011	0011	0021	0021
78200300	PRISMATIC CURB REFLECTOR	EACH	194	194				
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	47	47				
78200530	BARRIER WALL MARKERS, TYPE C	EACH	1,396	1,396				
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	16,200	16,200				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	560	560				
• 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2	2				
• 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	7,103	7,103				
• 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	357	357				
• 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	357	357				
• 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	207	207				
• 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,651	1,651				
• 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	49	49				
• 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	192	192				
• 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	2,640	2,640				
• 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	10	10				
• 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	1	1				
• 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	22	22				
• 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3	3				
• 81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	8,572	8,572				
• 81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	7,784	7,784				
• 81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	10,132	10,132				
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	23,518	23,518				
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	78	78				
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	5	5				
• 82105600	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	92	92				
• 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	12	12				
• 82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	2	2				
• 83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	19	19				
• 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	21	21				
• 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	31	31				
• 83502300	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 4	EACH	8	8				
• 83502400	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 6	EACH	10	10				
• 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	133	133				
• 83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	225	225				
• 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	76	76				

• DENOTES SPECIALTY ITEM

FILE NAME = H:\Dgn\sheet\sq07.dgn	USER NAME = EricG	DESIGNED - JWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION (46-2) I, HBR, VBR	COUNTY KANKAKEE	TOTAL SHEETS 558	SHEET NO. 10
PLOT SCALE = 1:50	CHECKED - EJC	REVISED -	SCALE: NONE					SHEET NO. 7 OF 11 SHEETS	STA.	TO STA.	CONTRACT NO. 66409	
PLOT DATE = 12/22/2010	DATE - 12/17/10	REVISED -				FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT						
Rev.												