	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
					0004	0011	0011	0021	0021
					ROADWAY	I-57 OVER IL ROUTE 50 SN 046-0014 (SB) SN 046-0015 (NB)	I-57 OVER ILLINOIS CENTRAL RR SN 046-0016 (SB) SN 046-0017 (NB)	SIGNALS (PAID 100% BY BRADLEY)	SAFETY (PAID 100% BY BRADLEY)
					90% FED / 10% STATE				
					URBAN				
•	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	55	55				
•	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	21	21				
•	84200804	REMOVAL OF POLE FOUNDATION	EACH	21	21				
•	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2	2				
•	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2	2				
•	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2	2				
•	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	5	5				
•	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	4	4				
•	85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1	1				
•	86000105	MASTER CONTROLLER (SPECIAL)	EACH	1	1				
•	86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	5	5				
•	86400100	TRANSCEIVER - FIBER OPTIC	EACH	5	5				
•	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	500	500				
•	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,845	2,845				
•	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	9,365	9,365				
•	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	319	319				
•	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	15,001	15,001				
•	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	1,602	1,602				
•	87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	886	886				
•	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2	2				
•	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	16	16				
•	87702700	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT. AND 50 FT.	EACH	1	1				
•	87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1	1				
•	87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	2	2				
•	87703010	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 56 FT.	EACH	1	1				
•	87703020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 58 FT.	EACH	1	1				
•	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	72	72				
•	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8	8				
•	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	80	80				
•	87900200	DRILL EXISTING HANDHOLE	EACH	12	12				
•	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	15	15				
•	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	18	18				
•	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3	3				
•	88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	6	6				
•	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	36	36				

• DENOTES SPECIALTY ITEM