	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY (URBAN)	CONSTRUCTION TYPE CODES: ROADWAY 0004	I-57 OVER IL 46-OUTE 50 SN 046-0014 (SB) SN 046-0015 (NB) 0011	I-57 OVER ILLINOIS CENTRAL RR SN 046-0016 (SB) SN 046-0017 (NB) 0011	SIGNALS 90% (PAID BY BRADLEY) 0021	SAFETY 10% (PAID BY BRADLEY) 0021
						90% FED. / 10% STATE			
•	X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1	1				
•	X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1				
•	X8410118	MAINTENANCE OF TEMPORARY LIGHTING SYSTEM	L SUM	1	1				
•	87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5,658	5,658				
•	87301004	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2,141	2,141				
•	X8730320	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,118	2,118				
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	110,580	110,580				
	Z0001058	AGGREGATE SUBGRADE 18"	SQ YD	1,066	1,066				
	Z0001060	AGGREGATE SUBGRADE 24"	SQ YD	1,979	1,979				
~~•~~	~~Z0007601~~	~~BUILDING REMOVAL NO. 1~~	~~L SUM~~	~~1~~	~~1~~				
~~•~~	~~Z0007602~~	~~BUILDING REMOVAL NO. 2~~	~~L SUM~~	~~1~~	~~1~~				
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
	Z0018800	DRAINAGE SYSTEM	L SUM	1			1		
	Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4			4		
	~~Z0018911~~	~~DRILL AND GROUT #6 TIE BARS~~	~~EACH~~	~~104~~	~~104~~				
	Z0022800	FENCE REMOVAL	FOOT	16,148	16,148				
	Z0026407	TEMPORARY SHEET PILING	SQ FT	5,722		5,012	710		
	Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	9	9				
	Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2				
	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4				
	Z0030270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	5	5				
	Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	13	13				
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
•	Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1	1				
•	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5,658	5,658				
	Z0034105	MATERIAL TRANSFER DEVICE	TON	7,438	7,438				
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	655		302	353		
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
~~•~~	~~Z0049801~~	~~REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1~~	~~L SUM~~						
~~•~~	~~Z0049802~~	~~REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 2~~	~~L SUM~~						
~~•~~	~~Z0049901~~	~~REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1~~	~~L SUM~~						
~~•~~	~~Z0049902~~	~~REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2~~	~~L SUM~~						
	Z0062456	TEMPORARY PAVEMENT	SQ YD	30,332	30,332				
	Z0065740	SLOTTED DRAIN 12" WITH VARIABLE SLOT	FOOT	2,490	2,490				
•	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2				

• DENOTES SPECIALTY ITEM

Rev

FILE NAME = I:\Dgn\sheets\sq010.dgn	USER NAME = EricG	DESIGNED - JWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE. 57	SECTION (46-2) I, HBR, VBR	COUNTY KANKAKEE	TOTAL SHEETS 558 / SHEET NO. 13
		DRAWN - JWM	REVISED -					CONTRACT NO. 66409	
	PLOT SCALE = 1:50	CHECKED - EJG	REVISED -		SCALE: NONE / SHEET NO. 10 OF 11 SHEETS / STA. / TO STA.	FED. ROAD DIST. NO. 3	ILLINOIS	FED. AID PROJECT	
	PLOT DATE = 12/22/2010	DATE - 12/17/10	REVISED -						