



**EXIT 315**  
 ILLINOIS  
**50**  
**Bradley  
 Bourbonnais**  
 1 MILE

STA. 242+20, RT @ I-57  
 GROUND MOUNT (168" X 180")  
 WITH STRUCTURAL STEEL  
 SIGN SUPPORT - BREAKAWAY

**Kankakee River  
 State Park**  
**Olivet Nazarene  
 University**  
 EXIT 315

STA. 250+50, RT @ I-57  
 GROUND MOUNT (180" X 156")  
 WITH STRUCTURAL STEEL  
 SIGN SUPPORT - BREAKAWAY

**EXIT 315**  
 ILLINOIS  
**50**  
**Bradley  
 Bourbonnais**  
 1/2 MILE

STA. 268+60, 86' RT @ I-57  
 GROUND MOUNT (168" X 180")  
 WITH STRUCTURAL STEEL  
 SIGN SUPPORT - BREAKAWAY

**Kankakee**  
 EXIT 315

STA. 278+50, 78' RT @ I-57  
 GROUND MOUNT (120" X 60")  
 WITH STRUCTURAL STEEL  
 SIGN SUPPORT - BREAKAWAY

- NOTES:
1. CONTRACTOR AND RESIDENT ENGINEER SHALL DETERMINE EXACT LENGTHS REQUIRED BEFORE ORDERING SUPPORTS
  2. RESIDENT ENGINEER TO DETERMINE FINAL PLACEMENT OF SIGN IN ACCORDANCE WITH STANDARD 720006.
  3. MINIMUM CLEAR HEIGHT IS 7 FEET FOR GROUND MOUNTED SIGNS.
  4. 4"x4" AND 4"x6" WOOD POST IS PAID FOR AS WOOD SIGN SUPPORT
  5. ALL NEW SIGN MATERIAL SHALL BE PROVIDED, ALL EXISTING EXTRUDED SIGN PANELS EXCEPT THE GENERAL SERVICES SIGNS THAT ARE TO BE RELOCATED SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND ALL OTHER SIGNS SHALL BE GIVEN TO THE DEPARTMENT.
  6. TWELVE INCH BY TWELVE INCH (12"x12") BLOCK-OUT WILL BE REQUIRED FOR SIGNS LOCATED IN CONCRETE MEDIANS.

FILE NAME = I:\dgn\sheets\si211.dgn	USER NAME = EricG	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-57 PROPOSED SIGNING PLAN</b>			F.A.I. RTE. 57	SECTION (46-2) I, HBR, VBR	COUNTY KANKAKEE	TOTAL SHEETS 558	SHEET NO. 200	
	PLOT SCALE = 1:200	CHECKED -	REVISED -					SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66409
	PLOT DATE = 12/22/2010	DATE = 12/17/10	REVISED -					FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT					