



**GENERAL NOTES**

SEE STANDARD 606301 AND PLAN SHEETS FOR STATION, OFFSETS, RADII, DIMENSIONS, AND DETAILS NOT SHOWN.

THE SIDEWALK SHOULD DRAIN TO THE LOW SIDE OF THE ISLAND. IF NECESSARY THE SIDEWALK SHALL BE SLOPED TO DRAIN AT A MAXIMUM 2% GRADE.

SEE THE INTERSECTION DETAIL SHEETS FOR THE TYPE OF CURB & GUTTER TO BE USED ON ISLANDS.

CURB & GUTTER ADJACENT TO THE WALKWAY IN THE INTERIOR OF THE ISLAND SHALL HAVE 6" GUTTER FLAGS.

THE SIDEWALK SHOULD NOT BE CLOSER THAN 36" FROM THE CORNER OF THE ISLAND.

KEYED LONGITUDINAL CONSTRUCTION JOINTS SHALL BE CONSTRUCTED WITHOUT TIE BARS.

MEDIANS AND LARGE ISLANDS SHALL CONSIST OF PCC SIDEWALK 5", CONCRETE MEDIAN SURFACE 4", AND COMBINATION CONCRETE CURB & GUTTER, TYPE M OR B OF THE SIZE SPECIFIED. MEDIAN ISLAND CAN ALSO BE SOLID CONCRETE MEDIANS.

THE INTERMEDIATE AND SMALL ISLANDS WILL BE MEASURED FOR PAYMENT FROM E.O.P. TO E.O.P. USING EITHER OPTION 1 OR OPTION 2, AS DIRECTED BY THE ENGINEER, AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQ. FT. FOR CONCRETE ISLAND (SPECIAL), WHICH SHALL INCLUDE THE COMBINATION CURB & GUTTER, SIDEWALK, AGGREGATE FILL, CONCRETE MEDIAN SURFACE, AND SOLID CONCRETE MEDIAN.

FILE NAME = I:\Dgn\Sheets\424-28.dgn	USER NAME = ErjaG	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>DISTRICT 3 DETAILS PCC ISLANDS AND MEDIANS ACCESSIBLE TO THE DISABLED</b>				F.A.I. RTE. 57	SECTION (46-2) I, HBR, VBR	COUNTY KANKAKEE	TOTAL SHEETS 558	SHEET NO. 387
	PLOT SCALE = 1:50	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO. 66409			
	PLOT DATE = 12/21/2018	CHECKED -	REVISED -		FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -										