

SUMMARY OF QUANTITIES			URBAN		
CODE NO.	ITEM	UNIT	80% FED.	0005	0005
			20% STATE	BUREAU COUNTY	LASALLE COUNTY
25200200	SUPPLEMENTAL WATERING	UNIT	3		3
20200100	EARTH EXCAVATION	CU YD	12		12
20400800	FURNISHED EXCAVATION	CU YD	6	6	
25200110	SODDING, SALT TOLERANT	SQ YD	348		348
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19169	4033	15136
40600300	AGGREGATE (PRIME COAT)	TON	20	2	18
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	41	9	32
40600525	LEVELING BINDER (HAND METHOD), N50	TON	69	15	54
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	1.0	1.0
40600990	TEMPORARY RAMP	SQ YD	720	35	686
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2126		2126
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12105	2598	9507
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	885	128	756
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	12733		12733
42400800	DETECTABLE WARNINGS	SQ FT	1384		1384
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	28007	18967	9040
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	96725	11065	85660
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	15183		15183
44000600	SIDEWALK REMOVAL	SQ FT	12748		12748
44200919	CLASS B PATCHES, TYPE II, 7 INCH	SQ YD	67		67
44200924	CLASS B PATCHES, TYPE III, 7 INCH	SQ YD	21		21
44200926	CLASS B PATCHES, TYPE IV, 7 INCH	SQ YD	153		153
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	445		445
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	345		345
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	69		69
44201299	DOWEL BARS 1 1/2"	EACH	1660		1660
44213204	TIE BARS 3/4"	EACH	56		56
44213100	PAVEMENT FABRIC	SQ YD	589		589
44213200	SAW CUTS	FOOT	5440		5440
48101200	AGGREGATE SHOULDERS, TYPE B	TON	330	216	114
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	1	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1.5	1.5
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.5	0.5
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1.0
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1.0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5963	1549	4414
X5619210	WATER VALVES TO BE ADJUSTED, SPECIAL	EACH	22		22
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	115		115

SUMMARY OF QUANTITIES			URBAN		
CODE NO.	ITEM	UNIT	80% FED.	0005	0005
			20% STATE	BUREAU COUNTY	LASALLE COUNTY
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	8371	892	7479
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	178875	53304	125571
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	49344	8442	40902
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	16998	4191	12807
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	20205	2112	18093
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2214	180	2034
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	994	258	736
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2790	297	2493
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	59327	17768	41559
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	14170	1380	12790
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	5666	1397	4269
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6735	704	6031
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	738	60	678
*78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	298		298
*78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	2278	1434	844
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1169	289	880
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1169	289	880
*88600100	DETECTOR LOOP, TYPE I	FOOT	4924	800	4124
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5282	1299	3983
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	2118		2118
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	9990	989	9001
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	2118		2118
Z0034105	MATERIAL TRANSFER DEVICE	TON	12105	2598	9507

*SPECIALTY ITEMS