

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS
				100% STATE
				ROADWAY
				0040
				RURAL
20200100	EARTH EXCAVATION	CU YD	55	55
20400800	FURNISHED EXCAVATION	CU YD	25	25
20800150	TRENCH BACKFILL	CU YD	8	8
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	100	100
44004250	PAVED SHOULDER REMOVAL	SQ YD	28	28
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4	4
48203100	HOT-MIX ASPHALT SHOULDERS	TON	20	20
50104650	SLOPE WALL REMOVAL	SQ YD	61	61
50105220	PIPE CULVERT REMOVAL	FOOT	78	78
54248510	CONCRETE COLLAR	CU YD	3	3
542D0235	PIPE CULVERT, CLASS D, TYPE 1 30"	FOOT	48	48
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
X0327237	CORRUGATED STEEL PIPE MULTIPLE END SECTIONS TRIPLE 30"	EACH	1	1