

SUMMARY OF QUANTITIES

100% STATE - 0014
HENDERSON

CODE NO.	ITEM	UNIT	RURAL	TOTAL
20200500	EARTH EXCAVATION (WIDENING)	CUYD	126	126
35600712	<i>HOT-MIX ASPHALT</i> BASE COURSE WIDENING, 9"	SQYD	504	504
50102400	CONCRETE REMOVAL	CUYD	19.6	19.6
50300255	CONCRETE SUPERSTRUCTURE	CUYD	19.7	19.7
50300300	PROTECTIVE COAT	SQYD	46.1	46.1
50800105	REINFORCEMENT BARS	POUND	948	948
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,180	2,180
50800515	BAR SPLICERS	EACH	41	41
52000110	PREFORMED JOINT STRIP SEAL	FOOT	100	100
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	2

FILE NAME = 68998.SN035-0037.0010.dgn

USER NAME = corpdm

DESIGNED - D CORP

REVISED -

DRAWN - D CORP

REVISED -

PLOT SCALE = 100.0000' / IN.

CHECKED - C JONES

REVISED -

PLOT DATE = 2/14/2011

DATE - 2/10/11

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 3 OF 18 SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	(116C1-BR1)-1;(111BR1)	HENDERSON	18	3
BRIDGE JOINT REPL.			CONTRACT NO. 68998	
ILLINOIS FED. AID PROJECT				