

| 70301000<br>WORK ZONE PAVEMENT MARKING REMOVAL     |       |
|--|-------|
| LOCATION   | SQ FT |
| STAGE 1  |       |
| STA. 45+40.10, 12.8' RT TO STA. 47+25.00, 5.5' LT  | 61.9  |
| STA. 47+25.00, 5.5' LT TO STA. 48+00.00, 5.5' LT   | 25.0  |
| STA. 46+99.85, 13.0' LT TO STA. 47+24.51, 15.5' LT | 8.3   |
| STA. 47+24.51, 15.5' LT TO STA. 48+00.00, 15.5' LT | 25.2  |
| STA. 52+00.00, 15.5' LT TO STA. 52+75.41, 15.5' LT | 25.1  |
| STA. 52+75.41, 15.5' LT TO STA. 53+05.03, 13.0' LT | 9.9   |
| STA. 52+00.00, 5.5' LT TO STA. 52+75.00, 5.5' LT   | 25.0  |
| STA. 52+75.00, 5.5' LT TO STA. 53+40.55, 0.0'      | 21.9  |
| STA. 53+40.55, 0.0' TO STA. 54+40.54, 13.3' RT     | 33.6  |
| STAGE 2  |       |
| STA. 45+77.42, 13.1' LT TO STA. 46+77.42, 0.0'     | 33.6  |
| STA. 46+77.42, 0.0' TO STA. 47+25.00, 4.0' RT      | 15.9  |
| STA. 47+25.00, 4.0' RT TO STA. 52+75.00, 4.0' RT   | 183.3 |
| STA. 52+75.00, 4.0' RT TO STA. 54+76.39, 12.6' LT  | 67.4  |
| STA. 47+02.62, 13.2' RT TO STA. 47+24.54, 15.0' RT | 7.3   |
| STA. 47+24.54, 15.0' RT TO STA. 52+75.45, 15.0' RT | 183.6 |
| STA. 52+75.45, 15.0' RT TO STA. 52+93.51, 13.5' RT | 6.0   |
| STOP BAR   |       |
| STA. 44+47.72, RT                                  | 25.7  |
| STA. 45+04.74 TO STA. 45+24.74, 19.8' RT           | 40.0  |
| STA. 55+00.55, LT                                  | 25.2  |
| SHORT TERM PAVEMENT MARKING                        |       |
| STA. 48+00.00 TO STA. 52+00.00                     | 13.3  |
| TOTAL  | 837.0 |

| 70400100<br>TEMPORARY CONCRETE BARRIER            |      |
|---|------|
| LOCATION  | FOOT |
| STA. 46+62.88, 4.8' RT TO STA. 53+37.10, 4.9' RT. | 675  |
| TOTAL   | 675  |

| 70400200<br>RELOCATE TEMPORARY CONCRETE BARRIER   |      |
|---|------|
| LOCATION  | FOOT |
| STA. 46+87.81, 4.3' LT TO STA. 53+12.20, 4.2' LT. | 625  |
| TOTAL   | 625  |

| 78100100<br>RAISED REFLECTIVE PAVEMENT MARKER |      |
|---|------|
| LOCATION                                      | EACH |
| STA 48+00.00                                  | 1    |
| STA 48+80.00                                  | 1    |
| STA 51+20.00                                  | 1    |
| STA 52+00.00                                  | 1    |
| TOTAL   | 4    |

| 78100105<br>RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) |      |
|--|------|
| LOCATION   | EACH |
| STA 49+60.00   | 1    |
| STA 50+40.00   | 1    |
| TOTAL  | 2    |

| 78200410<br>GUARDRAIL MARKERS, TYPE A |      |
|---------------------------------------|------|
| LOCATION                              | EACH |
| STA 46+70.53 TO STA 49+26.78, RT      | 4    |
| STA 48+13.68 TO STA 49+32.43, LT      | 4    |
| STA 50+67.58 TO STA 52+23.83, RT      | 4    |
| STA 50+73.22 TO STA 53+29.47, LT      | 4    |
| TOTAL                                 | 16   |

| 78201000<br>TERMINAL MARKER-DIRECT APPLIED |      |
|--|------|
| LOCATION                                   | EACH |
| STA. 46+70.53, RT                          | 1    |
| STA. 48+13.68, LT                          | 1    |
| STA. 52+23.83, RT                          | 1    |
| STA. 53+29.47, LT                          | 1    |
| TOTAL                                      | 4    |

| 78300100<br>PAVEMENT MARKING REMOVAL |       |
|--------------------------------------|-------|
| LOCATION                             | SQ FT |
| STA. 46+99.85 TO STA. 53+05.03, LT   | 201.7 |
| STA. 47+02.62 TO STA. 48+00.00, RT   | 32.5  |
| STA. 52+00.00 TO STA. 52+93.51, RT   | 31.2  |
| STA. 45+77.42 TO STA. 46+79.42       | 10.8  |
| STA. 53+23.32 TO STA. 54+76.39       | 12.8  |
| TOTAL                                | 289.0 |

| 78300200<br>RAISED REFLECTIVE PAVEMENT MARKER REMOVAL |      |
|---|------|
| LOCATION  | EACH |
| ENTIRE PROJECT  | 4    |
| TOTAL   | 4    |

| Z0030250<br>IMPACT ATTENUATORS,<br>TEMPORARY (NON-REDIRECTIVE) |      |
|--|------|
| LOCATION   | EACH |
| STA. 46+87.87  | 1    |
| STA. 54+12.20  | 1    |
| TOTAL  | 2    |

| Z0030350<br>IMPACT ATTENUATORS,<br>RELOCATE (NON-REDIRECTIVE) |      |
|---|------|
| LOCATION  | EACH |
| STA. 46+62.88   | 1    |
| STA. 53+37.10   | 1    |
| TOTAL   | 2    |

| 70100405<br>TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 |      |
|---|------|
| LOCATION  | EACH |
| ENTIRE PROJECT  | 1    |
| TOTAL   | 1    |

| 28000250<br>TEMPORARY EROSION CONTROL SEEDING |       |
|---|-------|
| LOCATION                                      | POUND |
| ENTIRE PROJECT                                | 450   |
| TOTAL   | 450   |

| 28000305<br>TEMPORARY DITCH CHECKS |      |
|------------------------------------|------|
| LOCATION                           | FOOT |
| STA. 48+50.00, LT                  | 10   |
| STA. 49+00.00, LT                  | 13   |
| STA. 49+43.50, LT                  | 10   |
| STA. 50+60.00, LT                  | 10   |
| STA. 50+95.00, LT                  | 10   |
| STA. 51+30.00, LT                  | 10   |
| STA. 51+65.00, LT                  | 10   |
| TOTAL                              | 73   |

| 78001110<br>PAINT PAVEMENT MARKING - LINE 4" |       |       |
|--|-------|-------|
| LOCATION                                     |       | FOOT  |
| STA. 46+82.81 TO STA. 53+17.31, LT           | SOLID | 634.5 |
| STA. 46+89.56 TO STA. 53+05.98, RT           | SOLID | 616.4 |
| STA. 48+00.00 TO STA. 52+00.00               | DASH  | 100.0 |
| TOTAL  |       | 1351  |

| 66700095<br>PERMANENT SURVERY MARKERS |      |
|---------------------------------------|------|
| LOCATION                              | EACH |
| STA. 49+25.00, P.T.                   | 1    |
| STA. 51+25.00, P.C.                   | 1    |
| TOTAL                                 | 2    |