# SUMMARY OF QUANTITIES (cont.)

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | | LOCATION OF WORK: | | FAP 804 U.S. 150 & University Ave. | FAP 804 U.S. 150 & Church St. | INTERCONNECT U.S. 150 & University Ave. | INTERCONNECT U.S. 150 & Church St. | FAP 804 U.S. 150 & University Ave. | FAP 804 U.S. 150 & Church St. |
| | | | | 100% State | 100% State | 100% State | 100% State | 100% City | 100% City |
| | | CONSTRUCTION TYPE CODE: | URBAN | 0021 | 0021 | 0021 | 0021 | 0021 | 0021 |
| CODE NO | ITEM | UNIT | TOTAL QUANTITY | QUANTITY | QUANTITY | QUANTITY | | QUANTITY | QUANTITY |
| 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 496.0 | | | | | 193.0 | 303.0 |
| 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 1,985.0 | 856.0 | 510.0 | | | 303.0 | 316.0 |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 2,216.0 | 1,092.0 | 1,124.0 | | | | |
| 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 1,487.0 | 549.0 | 938.0 | | | | |
| 87301515 | ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR | FOOT | 1,035.0 | 422.0 | 613.0 | | | | |
| 87301805 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C | FOOT | 159.0 | 77.0 | 82.0 | | | | |
| 87502640 | TRAFFIC SIGNAL POST, ALUMINUM 10 FT. | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 87502680 | TRAFFIC SIGNAL POST, ALUMINUM 14 FT. | EACH | 4.0 | 2.0 | 2.0 | | | | |
| 87502700 | TRAFFIC SIGNAL POST, ALUMINUM 16 FT. | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 87600200 | PEDESTRIAN PUSH-BUTTON POST, TYPE II | EACH | 4.0 | 2.0 | 2.0 | | | | |
| 87700170 | STEEL MAST ARM ASSEMBLY AND POLE, 26 FT. | EACH | 1.0 | 1.0 | | | | | |
| 87700180 | STEEL MAST ARM ASSEMBLY AND POLE, 28 FT. | EACH | 1.0 | | 1.0 | | | | |
| 87702840 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 22 FT. | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 87702930 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT. | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 24.8 | 12.4 | 12.4 | | | | |
| 87800200 | CONCRETE FOUNDATION, TYPE D | FOOT | 7.0 | 3.5 | 3.5 | | | | |
| 87800400 | CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER | FOOT | 40.0 | 20.0 | 20.0 | | | | |
| 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 26.0 | 13.0 | 13.0 | | | | |
| 88040070 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 4.0 | 2.0 | 2.0 | | | | |
| 88040090 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 14.0 | 7.0 | 7.0 | | | | |
| 88040160 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 88040260 | SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED | EACH | 2.0 | 1.0 | 1.0 | | | | |
| 88102717 | PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER | EACH | 16.0 | 8.0 | 8.0 | | | | |
| 88200100 | TRAFFIC SIGNAL BACKPLATE | EACH | 16.0 | 8.0 | 8.0 | | | | |
| 88500100 | INDUCTIVE LOOP DETECTOR | EACH | 8.0 | 4.0 | 4.0 | | | | |