

GUARDRAIL ITEMS SCHEDULE

STATION	TO	STATION	LENGTH	DIR.	LT/RT	SPBGR	GUARDRAIL	TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	GUARDRAIL	TERMINAL
						6' POSTS	REMOVAL	TERMINAL	TERMINAL	TERMINAL	TERMINAL	TERMINAL	MARKER	MARKER
						63000001	63200310	TY 6B	TY 6B (SPL)	TY 1(SPL)(FLARED)	TY 1(SPL) (TANGENT)	TY 2	TYPE A	DIRECT APPLIED
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH				
748+20.00		751+96.00	376.00	SB	LT	312.50	376.00	1					1	6
749+44.00		753+00.00	356.00	NB	RT	262.50	356.00	1			1		6	1
750+91.00		752+80.00	189.00	NB	LT	175	189.00	1		1			4	1
755+77.00		753+99.00	178.00	SB	RT	175	178.00	1		1			4	1
755+57.00		754+00.00	157.00	SB	LT	262.50	157.00	1			1		4	1
758+05.00		754+79.00	326.00	NB	RT	287.50	326.00	1				1	5	
166+00.00		179+25.00	1325.00	NB	RT	1262.50	1325.00			1			9	1
279+00.00		280+27.00	127.00	NB	RT	75.00	127.00				1		4	1
287+58.00		288+80.00	122.00	SB	LT	75.00	122.00				1		4	1
292+94.00		295+23.00	229.00	NB	LT	175	229.00	1		1			4	1
293+58.00		294+47.00	89.00	NB	RT	75.00	89.00	1			1		4	1
300+22.00		302+47.00	225.00	SB	RT	175	225.00	1		1			4	1
301+81.00		302+58.00	77.00	SB	LT	75.00	77.00	1			1		4	1
335+18.00		340+35.00	517.00	SB	LT	462.50	517.00		1			1	8	
338+27.00		341+25.00	298.00	NB	RT	287.50	298.00		1	1			5	1
339+27.00		341+18.00	191.00	NB	LT	175	191.00		1		1		4	1
342+90.00		344+64.00	174.00	SB	RT	175	174.00		1	1			4	1
342+70.00		346+00.00	330.00	SB	LT	287.50	330.00		1	1			6	1
TOTAL						4775	5286	10	5	8	7	6	89	15

FILE NAME =	USER NAME = leroyma	DESIGNED -	REVISED -
c:\pwork\pwork\leryma\d024443\0570273-sht-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0268' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/24/2011	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
GUARDRAIL ITEMS**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	HSIP FY2011I-1	MCLEAN	25	5
			CONTRACT NO. 70885	
ILLINOIS FED. AID PROJECT				