

SCHEDULE OF QUANTITIES

78300100 PAVEMENT MARKING REMOVAL (CONT.)

78300100 PAVEMENT MARKING REMOVAL (CONT.)

4" SKIP-DASH (YELLOW)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	E.B. & W.B.	889+23	-	905+84	2.0	830.5	276.6
FAP 693 (IL 9)	E.B. & W.B.	905+84	-	907+58	1.0	43.5	14.5
FAP 693 (IL 9) TOTAL =							291.0
FAP 704 (I-55 BUS)	-	-	-	-	-	-	-
TOTAL =							291.0

4" LANE LINE EXTENSION (WHITE)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	W.B.	910+77	-	912+54	1.0	59.0	19.6
FAP 693 (IL 9)	E.B.	913+08	-	915+38	1.0	76.7	25.5
FAP 693 (IL 9) TOTAL =							45.2
FAP 704 (I-55 BUS)	-	-	-	-	-	-	-
TOTAL =							45.2

4" SOLID (YELLOW-SINGLE)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	E.B. & W.B.	889+23	-	907+58	2.0	3670.0	1222.1
FAP 704 (I-55 BUS)	S.B.	258+78	-	277+05	1.0	1827.0	608.4
FAP 704 (I-55 BUS)	N.B.	256+67	-	277+05	1.0	2038.0	678.7
FAP 704 (I-55 BUS) TOTAL =							1287.0
TOTAL =							2509.2

4" SOLID (YELLOW-DOUBLE)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	E.B. & W.B.	909+22	-	913+08	1.0	772.0	257.1
FAP 693 (IL 9)	W.B.	912+54	-	916+58	1.0	808.0	269.1
FAP 693 (IL 9) TOTAL =							526.1
FAP 704 (I-55 BUS)	-	-	-	-	-	-	-
TOTAL =							526.1

4" SOLID (WHITE)

LOCATION	RAMP OR DIRECTION	STATION	TO	STATION	# OF LINES	LENGTH (FT.)	AREA (SQ. FT.)
FAP 693 (IL 9)	E.B.	906+48	-	907+58	1.0	110.0	36.6
FAP 693 (IL 9)	W.B.	909+22	-	910+77	1.0	155.0	51.6
FAP 693 (IL 9)	E.B.	915+38	-	916+52	1.0	114.0	38.0
FAP 693 (IL 9)	W.B.	153+77	-	154+98	2.0	242.0	80.6
FAP 693 (IL 9)	E.B.	155+44	-	157+95	1.0	251.0	83.6
FAP 693 (IL 9)	W.B.	157+87	-	158+87	1.0	100.0	33.3
FAP 693 (IL 9)	E.B.	158+97	-	163+12	1.0	415.0	138.2
FAP 693 (IL 9)	W.B.	164+39	-	168+90	1.0	451.0	150.2
FAP 693 (IL 9)	W.B.	168+56	-	169+89	1.0	133.0	44.3
FAP 693 (IL 9)	W.B.	168+97	-	170+79	2.0	364.0	121.2
FAP 693 (IL 9)	E.B.	171+59	-	172+67	1.0	108.0	36.0
FAP 693 (IL 9)	NW RAMP	10+62	-	11+16.5	1.0	54.5	18.1
FAP 693 (IL 9) TOTAL =							831.7
FAP 704 (I-55 BUS)	N.B. & S.B.	230+65	-	231+00	2.0	70.0	23.3
FAP 704 (I-55 BUS)	S.B.	232+46	-	238+02	1.0	556.0	185.1
FAP 704 (I-55 BUS)	S.B.	232+46	-	237+40	1.0	494.0	164.5
FAP 704 (I-55 BUS)	N.B.	237+61	-	242+09	1.0	448.0	149.2
FAP 704 (I-55 BUS)	N.B.	237+86	-	241+91	1.0	405.0	134.9
FAP 704 (I-55 BUS)	N.B.	242+81	-	246+46	1.0	365.0	121.5
FAP 704 (I-55 BUS)	S.B.	247+78	-	251+48	1.0	370.0	123.2
FAP 704 (I-55 BUS)	S.B.	252+15	-	257+33	1.0	518.0	172.5
FAP 704 (I-55 BUS)	S.B.	252+36	-	257+06	1.0	470.0	156.5
FAP 704 (I-55 BUS)	N.B.	271+44	-	277+05	1.0	561.0	186.8
FAP 704 (I-55 BUS)	S.B.	278+37	-	279+25	1.0	88.0	29.3
FAP 704 (I-55 BUS) TOTAL =							1446.9

TOTAL = 2278.6

PROJECT TOTAL = 8028.3

USE = 8029.0

* 693 & 704

** (129)I-2, (1,2)I, & (FAP 10)I

FILE NAME =	USER NAME = ceorlockbm	DESIGNED BMC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\d0243284\0570892-sht-schedule.dgn	DRAWN BMC	REVISOR -						*	**	MCLEAN	55	29
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISOR -			CONTRACT NO. 70892							
PLOT DATE = 12/29/2010	DATE 12-20-2010	REVISOR -			SCALE: N/A	SHEET NO. 8 OF 11 SHEETS	STA. -	TO STA. -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			