

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES

CODED PAY ITEM	DESCRIPTION	UNITS	TOTAL QUANTITY	IL 108	IL 111	SAFETY
				ROADWAY	ROADWAY	SAFETY
				80% FEDERAL	80% FEDERAL	90% FEDERAL
				20% STATE	20% STATE	10% STATE
				0005	0005	0021
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	62			62
20400800	FURNISHED EXCAVATION	CU YD	450	255	195	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	80		80	
28200200	FILTER FABRIC	SQ YD	80		80	
35800100	PREPARATION OF BASE	SQ YD	1,547	1,283.25	263.75	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	60	44.25	15.75	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	54	46.45	6.75	0.8
40600300	AGGREGATE (PRIME COAT)	TON	263	229	34	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	5573	4814	759	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,628	1,795	833	
40600990	TEMPORARY RAMP	SQ YD	665	426	239	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	11,329	9636.50	1,518	174.5
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	746	671.5	74.5	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9,095	4,220	4,875	
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	100	55	45	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	1,105	654	451	
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	302	164	138	
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	292	123	169	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,808	3,939.50	513	355.5
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	2,078			2,078
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	2,562.50	1,575	987.5	
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	400	25	87.5	287.5
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	18	8	8	2
63200310	GUARDRAIL REMOVAL	FOOT	3,766	2,081	1,516	169
64200105	SHOULDER RUMBLE STRIPS	FOOT	6,035			6,035
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2	
67100100	MOBILIZATION	L SUM	1	0.75	0.25	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.75	0.25	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.75	0.25	

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES

CODED PAY ITEM	DESCRIPTION	UNITS	TOTAL QUANTITY	IL 108	IL 111	SAFETY
				ROADWAY	ROADWAY	SAFETY
				80% FEDERAL	80% FEDERAL	90% FEDERAL
				20% STATE	20% STATE	10% STATE
				0005	0005	0021
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.25	0.25	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5			5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	13,730	11,986	1,744	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	121,857	108,692	13,165	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	80	80		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	60	60		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,510	1,318	192	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	121,857	108,692	13,165	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	80	80		
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	60	60		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	584	514	70	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	55	28	23	4
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	18	8	8	2
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	584	514	70	
X0326898	CENTER LINE - RUMBLE STRIP - 16"	FOOT	2,986			2,986
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	122,675	109,956	12,719	
Z0021922	SILICONE JOINT SEALER	FOOT	40		40	

* SPECIALTY ITEM

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
ei:\pwwork\pwwidat\laughlinr1\021544B\06	ZC36-shr-soq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 107.0000 / in.	CHECKED -	REVISED -
	PLOT DATE = Dec-17-2010 01:57:03PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	MACOUPIN	46	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72C36	

* FAP 765 & FAP 608
** IOTRS-3, IOTRS-1, IOTRS-3