

PAINT PAVEMENT MARKING-LINE SCHEDULE									
LOCATION			DESCRIPTION	LENGTH (FT)	SPACING	LINE 5"		LINE 6"	LINE 24"
STATION	TO	STATION				WHITE (FT)	YELLOW (FT)	WHITE (FT)	WHITE (FT)
<b>FAP 765 (IL 108 SOUTH)</b>									
STA. 80+00.00	TO	STA. 120+64.83	SOLID (EDGE LINE LT & RT)	4,064.83			8,019.66		
STA. 78+46.24	TO	STA. 80+15.00	SOLID (EAST & WEST BOUND NPZ)	168.76				337.52	
STA. 80+15.00	TO	STA. 90+80.00	SOLID (EAST BOUND NPZ)	1,065.00				1065.00	
STA. 80+15.00	TO	STA. 90+80.00	SKIP-DASH (CENTER WEST BOUND)	1,065.00	10' @40'			266.25	
STA. 90+80.00	TO	STA. 95+25.00	SKIP-DASH (CENTER EAST BOUND)	445.00	10' @40'			111.25	
STA. 90+80.00	TO	STA. 95+25.00	SOLID (WEST BOUND NPZ)	445.00				445.00	
STA. 95+25.00	TO	STA. 120+64.83	SOLID (EAST & WEST BOUND NPZ)	2,539.83				5079.66	
<b>STATION EQUATION STA. 120+64.83 BK. = STA. 122+78.03 AH.</b>									
STA. 122+78.03	TO	STA. 144+08.28	SOLID (EDGE LINE LT & RT)	2,130.25			4,100.50		
LIMPIE RD. RT. STA. 137+00.00 TO RT. STA. 138+60.00			SKIP-DASH (EDGE RT)	160.00	2' @ 8'			40.00	
STA. 122+78.03	TO	STA. 144+08.28	SOLID (EAST & WEST BOUND NPZ)	2,130.25				4260.50	
<b>STATION EQUATION STA. 144+08.28 BK. = STA. 145+88.98 AH.</b>									
STA. 145+88.98	TO	STA. 201+38.72	SOLID (EDGE LINE LT & RT)	5,549.74			11,099.48		
STA. 145+88.98	TO	STA. 146+00.00	SOLID (EAST & WEST BOUND NPZ)	11.02				22.04	
STA. 146+00.00	TO	STA. 157+00.00	SOLID (EAST BOUND NPZ)	1,100.00				1100.00	
STA. 146+00.00	TO	STA. 157+00.00	SKIP-DASH (CENTER WEST BOUND)	1,100.00	10' @40'			275.00	
STA. 157+00.00	TO	STA. 201+38.72	SKIP-DASH (CENTER )	4,438.72	10' @40'			1109.68	
<b>STATION EQUATION STA. 201+38.72 BK. = STA. 201+39.18 AH.</b>									
STA. 201+39.18	TO	STA. 249+99.94	SOLID (EDGE LINE LT & RT)	4,860.76			9,671.52		
STA. 201+39.18	TO	STA. 249+99.94	SKIP-DASH (CENTER )	4,860.76	10' @40'			1215.19	
<b>STATION EQUATION STA. 249+99.94 BK. = STA. 250+00.06 AH.</b>									
STA. 250+00.06	TO	STA. 332+89.53	SOLID (EDGE LINE LT & RT)	8,289.47			16,523.94		
STA. 250+00.06	TO	STA. 263+00.00	SKIP-DASH (CENTER )	1,299.94	10' @40'			324.99	
STA. 263+00.00	TO	STA. 269+50.00	SOLID (WEST BOUND NPZ)	650.00				650.00	
STA. 263+00.00	TO	STA. 269+50.00	SKIP-DASH (CENTER EAST BOUND)	650.00	10' @40'			162.50	
STA. 269+50.00	TO	STA. 276+00.00	SOLID (EAST BOUND NPZ)	650.00				250.00	
STA. 269+50.00	TO	STA. 276+00.00	SKIP-DASH (CENTER WEST BOUND)	650.00	10' @40'			162.50	
STA. 276+00.00	TO	STA. 325+00.00	SKIP-DASH (CENTER )	4,900.00	10' @40'			1225.00	
STA. 325+00.00	TO	STA. 332+89.53	SOLID (WEST BOUND NPZ)	789.53				789.53	
STA. 325+00.00	TO	STA. 332+89.53	SKIP-DASH (CENTER EAST BOUND)	789.53	10' @40'			197.38	
<b>STATION EQUATION STA. 332+89.53 BK. = STA. 332+89.64 AH.</b>									
STA. 332+89.64	TO	STA. 354+94.31	SOLID (EDGE LINE LT & RT)	2,204.67			4,249.34		
BEAR ROUGH HILLS RD. LT. STA. 346+90.00 TO LT. STA. 348+50.00			SKIP-DASH (EDGE LT)	160.00	2' @ 8'			40.00	
STA. 332+89.64	TO	STA. 354+94.31	SOLID (WEST BOUND NPZ)	160.00				160.00	
STA. 332+89.64	TO	STA. 354+94.31	SKIP-DASH (CENTER EAST BOUND)	160.00	10' @40'			40.00	

SHEET 1 OF 2

FAP 765 & FAP 608  
107RS-3,108RS-1,109RS-3

FILE NAME =	USER NAME = laughlinr	DESIGNED - JWC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\laughlinr\1\0215448\05	2C36-sht-schedule.dgn	DRAWN - JWC	REVISED -					•	**	MACOUPIN	46	18
PLOT SCALE = 48.0002' / in.	CHECKED - RSC	REVISED -	SCALE: 50		SHEET NO. OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
PLOT DATE = Dec-17-2010 01:58:34PM	DATE -	REVISED -						CONTRACT NO. 72C36				