

PAINT PAVEMENT MARKING-LINE SCHEDULE									
LOCATION			DESCRIPTION	LENGTH (FT)	SPACING	LINE 5"		LINE 6"	LINE 24"
STATION	TO	STATION				WHITE (FT)	YELLOW (FT)	WHITE (FT)	WHITE (FT)
STATION EQUATION STA. 354+94.31 BK. = STA. 355+54.89 AH.									
STA. 355+54.89	TO	STA. 372+88.00	SOLID (EDGE LINE LT & RT)	1,733.11		3,466.22			
STA. 355+54.89	TO	STA. 372+88.00	SOLID (EAST & WEST BOUND NPZ)	1,733.11			3,466.22		
STATION EQUATION STA. 372+88.00 BK. = STA. 373+50.40 AH.									
STA. 373+50.40	TO	STA. 413+68.06	SOLID (EDGE LINE LT & RT)	4,017.66		7,985.32			
STA. 373+50.40	TO	STA. 374+00.00	SOLID (EAST & WEST BOUND NPZ)	49.60			99.20		
STA. 374+00.00	TO	STA. 376+00.00	SOLID (EAST BOUND NPZ)	200.00			200.00		
STA. 374+00.00	TO	STA. 376+00.00	SKIP-DASH (CENTER WEST BOUND)	200.00	10' @40'		50.00		
STA. 376+00.00	TO	STA. 413+68.06	SKIP-DASH (CENTER)	3,768.06	10' @40'		942.01		
STATION EQUATION STA. 413+68.06 BK. = STA. 413+68.64 AH.									
STA. 413+68.64	TO	STA. 479+78.80	SOLID (EDGE LINE LT & RT)	6,610.16		13,110.32			
STA. 413+68.64	TO	STA. 432+00.00	SKIP - DASH (CENTER)	1,831.36	10' @40'		457.84		
STA. 432+00.00	TO	STA. 439+50.00	SOLID (WEST BOUND NPZ)	750.00			750.00		
STA. 432+00.00	TO	STA. 439+50.00	SKIP-DASH (CENTER EAST BOUND)	750.00	10' @40'		187.50		
STA. 439+50.00	TO	STA. 447+15.00	SOLID (EAST BOUND NPZ)	765.00			765.00		
STA. 439+50.00	TO	STA. 447+15.00	SKIP-DASH (CENTER WEST BOUND)	765.00	10' @40'		191.25		
STA. 447+15.00	TO	STA. 465+75.00	SKIP - DASH (CENTER)	1,860.00	10' @40'		465.00		
STA. 465+75.00	TO	STA. 473+00.00	SOLID (WEST BOUND NPZ)	725.00			725.00		
STA. 465+75.00	TO	STA. 473+00.00	SKIP-DASH (CENTER EAST BOUND)	725.00	10' @40'		181.25		
STA. 473+00.00	TO	STA. 479+50.00	SOLID (EAST & WEST BOUND NPZ)	650.00			1300.00		
RT. STA. 479+50			STOP BAR						26.00
FAP 765 (IL 108 NORTH)									
STA. 526+61.81	TO	STA. 533+00.00	SOLID (EDGE LINE LT & RT)	638.19		1,276.38			
STA. 526+61.81	TO	STA. 533+00.00	SKIP - DASH (CENTER)	638.19	10' @ 40'		159.55		
LT. STA. 526+85			STOP BAR						34.00
FAP 608 (IL 111)									
STA. 884+62.00	TO	STA. 942+91.74	SOLID (EDGE LINE LT & RT)	5,829.74		11,424.00			
STA. 884+62.00	TO	STA. 942+91.74	SOLID (EAST & WEST BOUND NPZ)	5,829.74			1457.44		
STATION EQUATION STA. 942+91.74 BK. = STA. 943+00.00 AH.									
STA. 943+00.00		STA. 943+71.00	SOLID (EDGE LINE LT & RT)	71.00		142.00			
STA. 943+00.00		STA. 943+71.00	SOLID (EAST & WEST BOUND NPZ)	71.00			142.00		
SUB-TOTAL						91,068.68	30,788.25		
TOTAL						121857.00	80.00	60.00	

NOTE: QUANTITIES FOR TEMPORARY PAVEMENT MARKING-LINE
SAME AS PAINT PAVEMENT MARKING-LINE

SHEET 2 OF 2

FILE NAME =	USER NAME = laughlinr1	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pw\work\p\dot\laughlinr1\d0215448\06	2C36-sht-schedule.dgn	DRAWN - JWC	REVISED -					*	**	MACOUPIN	46	19
	PLOT SCALE = 48,0037' / in.	CHECKED - RSC	REVISED -		SCALE: 50	SHEET NO. OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72C36		
	PLOT DATE = Dec-17-2010 01:58:43PM	DATE -	REVISED -							ILLINOIS FED. AID PROJECT		

* FAP 765 & FAP 608
** 107RS-3,108RS-1,109RS-3