

CHRISTIAN CO.

SIGN LOCATION	ROUTE	SIGN PANEL TY 1 (SQ FT)	SIGN PANEL TY 2 (SQ FT)	REMOVE SIGN PANEL, TY 1 (SQ FT)	RELOCATE SIGN PANEL ASSEMBLY TY B (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	NUMBER OF POST	HEIGHT ABOVE THE GROUND TO THE BOTTOM OF SIGN (FOOT)	SIGN DESCRIPTION	REMARKS
#1	IL 29	9.0				16.0	1	7.0	W3-3 (3636) "SIGNAL AHEAD"	
#2	IL 104	9.0				16.0	1	7.0	W3-3 (3636) "SIGNAL AHEAD"	
			15.0			30.0	2	7.0	R3-8 (6036) "DIRECTIONAL ARROWS"	
#3	IL 29	9.0				16.0	1	7.0	W3-3 (3636) "SIGNAL AHEAD"	
#4	IL 29				10.5			7.0		RELOCATE EXISTING SIGNS
					16.5			7.0		RELOCATE EXISTING SIGNS
#5	IL 29	9.0				16.0	1	7.0	W3-3 (3636) "SIGNAL AHEAD"	
#6	IL 29	9.0				16.0	1	7.0	W3-3 (3636) "SIGNAL AHEAD"	
#7	MT. AUBURN RD	3.0				13.0	1	6.0	W1-8 (1824) "CHEVRONS"	TWO SIGNS PER LOCATION IN CURVE #1
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
		3.0				13.0	1	6.0		
SUBTOTAL		117.0	15.0	18.0	27.0	227.0	16			