



**MEDIAN SUBSURFACE DRAIN EXTENSION
DETAIL AT CROSSOVER**

PAVING SCHEDULE	AGGREGATE BASE COURSE, TYPE B		HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 14"	PAVED SHOULDER REMOVAL	AGGREGATE SHOULDERS, TYPE B	PAINT PAVEMENT MARKING - LINE 4" (YELLOW)	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	DRUMS	
	STATION TO	STATION	TON	SQ YD	SQ YD	TON	FOOT	FOOT	FOOT	SQ FT	EACH
WEST CROSSOVER											
573+00.00	TO	90+50.00	1039.4	4563.3	1739.2	431.8	1304.4	52.2	1304.4	17.4	19.0
EAST CROSSOVER											
168+75.00	TO	181+50.00	1024.9	4499.8	1700.0	422.1	1275.0	51.0	1275.0	17.0	19.0
TOTALS			2064.0	9063.0	3439.0	854.0	2579.0	103.0	2579.0	34.0	38.0

UNDERDRAIN SCHEDULE	PIPE UNDERDRAIN 4" (SPECIAL)		REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN
	FOOT	EACH	
WEST CROSSOVER			
LT 575+00	5.0	1.0	
RT 80+50	10.0	1.0	
LT 90+00	5.0	1.0	
RT 90+15	5.0	1.0	
EAST CROSSOVER			
LT 172+00	10.0	1.0	
RT 172+25	10.0	1.0	
LT 173+30	10.0	1.0	
TOTALS		55.0	7.0

SEEDING SCHEDULE	SEEDING, CLASS 2 (SPECIAL)	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NURTIENT*	PHOSPHORUS FERTILIZER NURTIENT*	POTASSIUM FERTILIZER NURTIENT*	MULCH, METHOD 2*	AGRICULTURAL GROUND LIMESTONE*		
	STATION TO	STATION	ACRE	POUND	POUND	POUND	ACRE	TON	
WEST CROSSOVER									
573+00.0	TO	90+50.0	0.52	52.40	47.16	47.16	47.16	0.52	1.05
EAST CROSSOVER									
168+75.0	TO	178+50.0	0.41	40.50	36.45	36.45	36.45	0.41	0.81
TOTAL =			0.90	93.00	84.00	84.00	84.00	0.90	2.00

* QUANTITY FOR INFORMATION ONLY INCLUDED IN COST OF SEEDING, CLASS 2 (SPECIAL)