

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF BEARING AND JOINT REPLACEMENT AND OTHER WORK NECESSARY TO COMPLETE THE PROJECT. MEDIAN REMOVAL AND REPLACEMENT IS SHOWN IN TWO STAGES. THE CONTRACTOR MAY ELECT TO PERFORM ALL MEDIAN REMOVAL AND REPLACEMENT BEFORE BEGINNING STAGE 1 CONSTRUCTION.

WET REFLECTIVE TEMPORARY TAPE SHALL BE USED DURING STAGE 1 & 2. PAINT PAVEMENT MARKINGS SHALL BE APPLIED TO THE WESTBOUND LANES BEFORE RESTORING TRAFFIC TO THE NORMAL PATTERN AFTER STAGE 2 IS COMPLETE. PAINT PAVEMENT MARKINGS SHALL BE APPLIED TO THE EASTBOUND LANES IMMEDIATELY THEREAFTER.

THE REFLECTIVE LENS OF ALL RAISED REFLECTIVE PAVEMENT MARKERS IN CONFLICT WITH THE STAGE TRAFFIC CONTROL SHALL BE REMOVED PRIOR TO STAGE 1 CONSTRUCTION. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR RAISED REFLECTIVE PAVEMENT MARKERS, REFLECTOR REMOVAL.

REMOVAL OF THE 4" THICK MEDIAN SURFACE WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR CONCRETE MEDIAN SURFACE REMOVAL. THIS ITEM SHALL BE CONSTRUCTED ACCORDING TO SECTION 440 OF THE STANDARD SPECIFICATIONS.

MATERIAL EXCAVATED FROM MEDIAN SHALL BE STOCKPILED AND REPLACED AT COMPLETION OF STAGE CONSTRUCTION WORK. COST OF EXCAVATION, STOCKPILING, AND REPLACEMENT OF EXCAVATED MATERIAL SHALL BE INCLUDED IN THE UNIT PRICE FOR PCC BASE COURSE.

THE UNIT PRICE FOR PCC BASE COURSE SHALL INCLUDE THE COST OF REMOVAL OF THAT ITEM AFTER THE COMPLETION OF STAGE 2.

THE UNIT PRICE FOR COMBINATION CONCRETE CURB & GUTTER TYPE B9.24 SHALL INCLUDE TWO 25 FOOT LONG TRANSITIONS TO TYPE B6.24 CURB & GUTTER.

FIELD MARKINGS OF UNDERGROUND UTILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

INDEX OF SHEETS

SHEET NO	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS
3	SUMMARY OF QUANTITIES
4-7	TYPICAL SECTIONS
8	SCHEDULES
9-15	STAGE 1 STAGING DETAILS
16-22	STAGE 2 STAGING DETAILS
23-32	STRUCTURAL SHEETS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606301-04	PC CONCRETE ISLANDS AND MEDIANS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS >= 45 MPH
701606-07	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701801-04	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS

FILE NAME = c:\pwork\pwork\teasleyck\d0209576\07	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND INDEX OF SHEETS	F.A.P. RTE. 320	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	4491-shr-gennote.dgn	DRAWN -	REVISED -			Macon	32	2		
	PLOT SCALE = 50.0000 1/1 IN.	CHECKED -	REVISED -			CONTRACT NO. 74491				
	PLOT DATE = 2/24/2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.