

RESURFACING SCHEDULE			LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	LEVELING BINDER (MACHINE METHOD), N70	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP	TEMPORARY RAMP, SPECIAL
STATION	TO	STATION														
			FOOT	FOOT	SQ FT	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	UNIT	TON	SQ YD	SQ YD
50+04.50	TO	50+46.50	42.0	VAR	1596.6	0.0	0.0	177.4	35.4	0.4	14.9	7.5	0.0	0.0	50.6	5.0
50+46.50	TO	59+42.00	895.5	22.0	19701.0	0.0	0.0	2189.0	437.8	4.4	183.9	91.9	0.0	0.0	0.0	22.7
59+42.00	TO	60+30.00	88.0	23.0	2024.0	0.0	0.0	224.9	45.0	0.4	18.9	9.4	0.0	0.0	0.0	2.8
60+30.00	TO	61+80.00	150.0	24.0	3600.0	0.0	0.0	400.0	80.0	0.8	35.3	16.8	1.5	2.4	0.0	0.0
61+80.00	TO	62+10.00	30.0	24.0	720.0	80.0	0.0	0.0	16.0	0.2	7.4	3.4	0.6	1.5	0.0	0.0
62+10.00	TO	333+86.00	27176.0	24.0	652224.0	72469.3	0.0	0.0	14493.8	144.9	6701.4	3043.7	526.3	1832.4	0.0	0.0
333+86.00	TO	334+16.00	30.0	24.0	720.0	80.0	0.0	0.0	16.0	0.2	7.4	3.4	0.6	1.5	0.0	0.0
334+16.00	TO	349+04.54	1488.5	24.0	35725.0	0.0	0.0	3969.4	793.8	7.9	333.4	166.7	0.0	0.0	0.0	4.4
349+04.54	TO	349+34.54	30.0	VAR	912.3	101.4	0.0	0.0	20.2	0.2	8.5	0.8	0.0	0.0	17.2	0.0
349+34.54	TO	351+86.46	251.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
351+86.46	TO	352+16.46	30.0	VAR	911.8	101.3	0.0	0.0	20.2	0.2	8.5	0.8	0.0	0.0	17.2	0.0
352+16.46	TO	361+10.00	893.5	24.0	21445.0	0.0	0.0	2382.8	476.6	4.8	200.2	100.1	0.0	0.0	0.0	5.6
361+10.00	TO	361+40.00	30.0	24.0	720.0	80.0	0.0	0.0	16.0	0.2	7.0	3.4	0.3	0.8	0.0	0.0
361+40.00	TO	366+53.00	513.0	24.0	12312.0	1368.0	0.0	0.0	273.6	2.7	125.7	57.5	9.2	32.2	0.0	0.0
366+53.00	TO	368+26.00	173.0	24.0	4152.0	461.3	0.0	0.0	92.2	0.9	41.2	19.4	1.0	3.5	0.0	0.0
368+26.00	TO	471+70.00	10344.0	24.0	248256.0	27584.0	0.0	0.0	5516.8	55.2	2552.5	1158.5	201.8	704.7	0.0	0.0
471+70.00	TO	472+00.00	30.0	24.0	720.0	80.0	0.0	0.0	16.0	0.2	7.4	3.4	0.6	1.5	0.0	0.0
472+00.00	TO	480+89.50	889.5	23.0	20458.5	0.0	0.0	2273.2	454.6	4.5	200.7	95.5	8.4	13.3	21.8	18.3
480+89.50	TO	480+98.60	9.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
480+98.60	TO	482+87.50	188.9	22.0	4155.8	0.0	0.0	461.8	92.4	0.9	38.8	19.4	0.0	0.0	21.0	0.0
482+87.50	TO	483+48.50	61.0	VAR	1807.6	0.0	0.0	200.8	40.2	0.4	16.9	8.4	0.0	0.0	18.7	0.0
SIDEROAD/WIDENED SHOULDER AREA																
59+42.00	TO	61+79.26	237.3	VAR	4254.9	0.0	472.8	0.0	94.6	0.9	39.7	0.0	0.0	0.0	0.0	3.3
TOTALS																
						102406.0	473.0	12280.0	23032.0	231.0	10550.0	4810.0	751.0	2594.0	147.0	63.0