

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODES			
				ROADWAY 0004	SN 082-0038 0011	BIKE TRAIL 0038	SIGNALS 0021
58700300	CONCRETE SEALER	SQ FT	2102		2102		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	139		139		
60105000	PIPE DRAINS, CORRUGATED STEEL OR ALUMINUM ALLOY 12"	FOOT	723	723			
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	166		166		
60209520	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND LID	EACH	2	2			
60211660	CATCH BASINS, TYPE D, 3'-DIAMETER, SPECIAL FRAME AND GRATE	EACH	2	2			
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	3	3			
60240312	INLETS, TYPE B, TYPE 11V FRAME AND GRATE	EACH	3	3			
60500060	REMOVING INLETS	EACH	2	2			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	843	843			
60619100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SQ FT	2249	2249			
60801012	FLAP GATE 12"	EACH	2	2			
60900115	TYPE B INLET BOX, STANDARD 609001	EACH	4	4			
60900515	CONCRETE THRUST BLOCKS	EACH	12	12			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	387.5	387.5			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	530	530			
64200105	SHOULDER RUMBLE STRIPS	FOOT	782	782			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30			
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	30	30			
67100100	MOBILIZATION	L SUM	1	1			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	10	10			
* 73000100	WOOD SIGN SUPPORT	FOOT	29	29			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	970	970			
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8962	8962			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	38	38			
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	26	26			
78200300	PRISMATIC CURB REFLECTOR	EACH	82	82			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	17	17			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	16			16	
81400115	HANDHOLE TO BE ADJUSTED	EACH	1			1	
88600100	DETECTOR LOOP, TYPE I	FOOT	72			72	
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	18		18		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODES			
				ROADWAY 0004	SN 082-0038 0011	BIKE TRAIL 0038	SIGNALS 0021
Z0016702	DETOUR SIGNING	L SUM	1	1			
X0325626	HIGH LOAD MULTI-ROTATION BEARINGS, FIXED - 800K	EACH	7		7		
X0325629	HIGH LOAD MULTI-ROTATION BEARINGS, FIXED - 1250K	EACH	14		14		
X0326707	TEMPORARY PROTECTION SYSTEM FOR BICYCLE TRAFFIC	L SUM	1			1	
X5041800	CONCRETE ANCHORS	EACH	41	41			
X5080600	MECHANICAL SPLICERS	EACH	792		792		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0018800	DRAINAGE SYSTEM	L SUM	1		1		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
Z0076600	TRAINEES	HR	2,500	2,500			

0042

CB Coombe-Bloxdorf P.C.
- CIVIL ENGINEERS -
- STRUCTURAL ENGINEERS -
- LAND SURVEYORS -
Design Firm License No. 184-002703

FILE NAME =	USER NAME = CFC...	DESIGNED -	REVISED -
...004-005-D876882-summary-of-quantities.dgn		DRAWN -	REVISED -
	PLOT SCALE = 1:8000 ' / IN.	CHECKED -	REVISED -
CB JOB NO 09021	PLOT DATE = 8/5/2018	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	64-1VBR	ST. CLAIR	259	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76882	