

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

URBAN

80% FEDERAL
 20% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ALTON 3P	0005 MADISON COUNTY 3P	0004 MADISON COUNTY 3R				
60500105	FILLING MANHOLES	EACH	16			16				
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	2200	2200						
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	2470	1920	550					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	16600	12800	3800					
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	950	175	775					
63000015	STEEL PLATE BEAM GUARDRAIL, TYPE D	FOOT	175		175					
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2		2					
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	2	2					
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	2	2					
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2		2					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	6	2	2				
67100100	MOBILIZATION	L SUM	1	0.6	0.2	0.2				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.6	0.2	0.2				
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	0.6	0.2	0.2				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.6	0.2	0.2				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.6	0.2	0.2				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.6	0.2	0.2				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	15		45				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15756	13356	720	1680				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3645	3083.4	62.4	499.2				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	114769	88012	11257	15500				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1756	1756						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	879.4	693	62.4	124				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1313	1113	60	140				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	36			36				
* 73000100	WOOD SIGN SUPPORT	FOOT	60			60				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1485	923.4	62.4	499.2				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	114697	88012	11185	15500				

* SPECIALTY ITEM

FILE NAME =
 USER NAME = karlesal
 DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 2/7/2011

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	132-2,3,4 133-1RS	MADISON	122	5
CONTRACT NO. 76B80				
ILLINOIS FED. AID PROJECT				