

PARTIAL DEPTH PATCHING (CONTINUED FROM PREVIOUS SHEET)

MILE STATION (MI.)	DIRECTION (EB / WB)	LANE DESCRIPTION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PARTIAL DEPTH REMOVAL, 2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
3.61	WB	PL	6	12	8.0	8.0	0.9
3.79	WB	PL	20	6	13.3	13.3	1.5
3.79	WB	DL	20	6	13.3	13.3	1.5
3.84	WB	PL	6	12	8.0	8.0	0.9
3.86	WB	PL	100	12	133.3	133.3	14.9
3.86	WB	DL	100	12	133.3	133.3	14.9
3.87	WB	DL	10	6	6.7	6.7	0.7
3.87	WB	PL	10	6	6.7	6.7	0.7
3.88	WB	DL	20	12	26.7	26.7	3.0
3.89	WB	DL	8	12	10.7	10.7	1.2
3.90	WB	DL	8	6	5.3	5.3	0.6
3.90	WB	PL	8	6	5.3	5.3	0.6
3.91	WB	DL	10	12	13.3	13.3	1.5
3.91	WB	PL	20	12	26.7	26.7	3.0
3.94	WB	DL	20	12	26.7	26.7	3.0
3.94	WB	PL	20	12	26.7	26.7	3.0
3.97	WB	DL	6	12	8.0	8.0	0.9
3.97	WB	PL	6	12	8.0	8.0	0.9
3.98	WB	DL	8	12	10.7	10.7	1.2
3.98	WB	PL	8	12	10.7	10.7	1.2
3.99	WB	DL	8	12	10.7	10.7	1.2
3.99	WB	PL	8	12	10.7	10.7	1.2
4.01	WB	DL	8	12	10.7	10.7	1.2
4.01	WB	PL	8	12	10.7	10.7	1.2
4.03	WB	DL	12	12	16.0	16.0	1.8
4.03	WB	PL	12	12	16.0	16.0	1.8
4.04	WB	PL	8	12	10.7	10.7	1.2
4.05	WB	PL	8	12	10.7	10.7	1.2
4.06	WB	PL	100	12	133.3	133.3	14.9
4.08	WB	PL	6	12	8.0	8.0	0.9
4.08	WB	DL	6	12	8.0	8.0	0.9
4.09	WB	PL	8	12	10.7	10.7	1.2
4.09	WB	DL	8	12	10.7	10.7	1.2
4.11	WB	PL	100	12	133.3	133.3	14.9
4.11	WB	DL	24	12	32.0	32.0	3.6
4.13	WB	DL	50	12	66.7	66.7	7.5
0.52	EB	MIDDLE LANE	6	12	8.0	8.0	0.9
0.52	EB	2ND LANE	40	12	53.3	53.3	6.0
0.72	EB	LEFT LANE	120	12	160.0	160.0	17.9
0.76	EB	LEFT TURN LANE	6	12	8.0	8.0	0.9

SCHEDULE CONTINUED (SEE NEXT SHEET)

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -					785	(132-2,3,4, 133-1)RS	MADISON	122	32
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 76B80				
	PLOT DATE = #DATE#	DATE -	REVISED -		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT							