

SUMMARY OF QUANTITIES

MADISON Co. BOND Co.

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	MADISON Co. BOND Co.		SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		URBAN 0004 060-0319, 060-0320	RURAL 0004 003-0023	CODE NO	ITEM	UNIT		TOTAL QUANTITIES		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.2	1.1	0.1							
40600300	AGGREGATE (PRIME COAT)	TON	4	3.2	0.8							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	206	206								
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	438	438								
40600990	TEMPORARY RAMP	SQ YD	124	124								
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	209	166.5	42.5							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	294	59.3	234.7							
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1153	1153								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	14	12.4	1.6							
48203100	HOT-MIX ASPHALT SHOULDERS	TON	112	112								
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	412.5	412.5								
63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	8	8								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2							
67100100	MOBILIZATION	L SUM	1	0.7	0.3							
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1							
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1								
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1								
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	180	150.1	29.9							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	59.8	49.8	10							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1825	1431.2	393.8							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	22	17	5							
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	13	13								
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	3	3								
* 78200430	GUARDRAIL MARKERS, TYPE C	EACH	3	3								
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	22	17	5							
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1								
Z0038114	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/4"	SQ YD	339	339								
Z0038121	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2"	SQ YD	259	259								

*SPECIALTY ITEM

* VARIOUS
** D-8 BRIDGE APPROACH 2011-1
*** BOND & MADISON