

STANDARDS

- 000001-06
- 001001-02
- 442101-07
- 635011-02
- 701400-05
- 701402-08
- 701901-01
- 704001-06

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. A QUANTITY OF 2050 FEET OF "TEMPORARY PAVEMENT MARKING - LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER ACROSS THE STRUCTURES AND APPROACHES FOR BOTH STAGES.
4. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - \* AT&T ILLINOIS
  - \* CITY OF GREENVILLE

MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY \*. NON- J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
5. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND ENDING OF THE PROJECT AND AT ALL INTERSECTING SIDE ROADS AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.
6. THE RE/RT SHALL RECORD AND DOCUMENT ALL EXISTING PAVEMENT MARKINGS AND THEIR LOCATIONS PRIOR TO REMOVAL OF APPROACH PAVEMENT. AFTER APPROACH PAVEMENT HAS BEEN COMPLETED, THE PROPOSED PAVEMENT MARKING SHALL BE PLACED AT THE EXISTING DOCUMENTED LOCATIONS.

STAGE CONSTRUCTION NOTES

STAGE I WESTBOUND: PLACE 425 FEET OF TEMPORARY CONCRETE BARRIER AND 1 EACH IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 AS SHOWN ON STANDARD 701402-08.

STAGE II WESTBOUND: RELOCATE 425 FEET OF TEMPORARY CONCRETE BARRIER. RELOCATE 1 EACH IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 AS SHOWN ON STANDARD 701402-08.

STAGE I EASTBOUND: PLACE 400 FEET OF TEMPORARY CONCRETE BARRIER AND 1 EACH IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 AS SHOWN ON STANDARD 701402-08.

STAGE II EASTBOUND: RELOCATE 400 FEET OF TEMPORARY CONCRETE BARRIER. RELOCATE 1 EACH IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 AS SHOWN ON STANDARD 701402-08.

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>STANDARDS, GENERAL NOTES &amp; COMMITMENTS</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -					70	3-4BT-1	BOND	35	2
	PLOT DATE = #DATE#	DATE -	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 76E23			
								FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			