

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
				0014 100% STATE	
42001300	PROTECTIVE COAT	SQ YD	590	590	
<del>44201011</del>	<del>CLASS B PATCHES, TYPE III, 13 INCH</del>	<del>SQ YD</del>	<del>109.8</del>	<del>109.8</del>	
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	124	124	
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	165	165	
44213208	TIE BARS 1/4"	EACH	159	159	
<del>44201296</del>	<del>DEFORMED BARS - EXPANSION JOINT</del>	<del>EACH</del>	<del>67</del>	<del>67</del>	
44201299	DOWEL BARS 1 1/2"	EACH	159	159	
50102400	CONCRETE REMOVAL	CU YD	210.8	210.8	
50300225	CONCRETE STRUCTURES	CU YD	23.3	23.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	202.8	202.8	
50300260	BRIDGE DECK GROOVING	SQ YD	526	526	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	35370	35370	
50800515	BAR SPlicERS	EACH	186	186	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	165	165	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1217	1217	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	400	400	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2012.5	2012.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2012.5	2012.5	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	472	472	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	745	745	
Z0030250	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

\*SPECIALTY  
ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
#FILE#		DRAWN -	REVISED -
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -
	PLOT DATE = #DATE#	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE    SHEET NO. 1 OF 1 SHEETS    STA.    TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	3-4B1-1	BOND	35	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76E23	