

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0014	
				100% STATE	
XX008458	CONCRETE WEARING SURFACE, (VARIABLE DEPTH)	CU YD	34.4	34.4	
50102400	CONCRETE REMOVAL	CU YD	2.9	2.9	
50300260	BRIDGE DECK GROOVING	SQ YD	249	249	
50300300	PROTECTIVE COAT	SQ YD	249	249	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3530	3530	
50800515	BAR SPLICERS	EACH	77	77	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	35	35	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	54	54	
70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	84	84	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	28	28	
X78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1880	1880	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1	1	
78100300	REPLACEMENT REFLECTOR	EACH	5	5	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	627	627	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6	
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	1880	1880	
Z0004540	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ YD	245	245	
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	33	33	
Z0032700	KEYWAY REPAIR	FOOT	170	170	

GENERAL NOTES:

1. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - AMERENIP (GAS & ELECTRIC)
  - FOUNTAIN WATER DISTRICT
  - HARRISONVILLE TELEPHONE COMPANY
  - VERIZON BUSINESS
MEMBERS OF J.U.L.I.E. (800) 892-0123 OR 811 ARE INDICATED BY AN \*. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
3. TEMPORARY PAVEMENT MARKINGS SHOWN ON TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 SHALL BE PAVEMENT MARKING TAPE, TYPE III. THE COST OF PAVEMENT MARKING TAPE, TYPE III SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.

PERTINENT INFORMATION

THERE ARE TWO FIELD ENTRANCES LOCATED DIRECTLY TO THE WEST OF THE STRUCTURE. BOTH ENTRANCES ARE OWNED BY BLUFFSIDE DAIRY FARM. THE CONTRACTOR SHALL COORDINATE WITH BLUFFSIDE DAIRY FARM FOR ACCESS INTO THEIR FIELD ENTRANCES

BLUFFSIDE DAIRY FARM, INC.  
2160 STATE ROUTE 156  
WATERLOO, IL 62298  
618-939-6069

COMMITMENTS

NONE

FILE NAME *	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES, GENERAL NOTES AND COMMITMENTS</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		829	102BR-3-1	MONROE	6	2			
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		CONTRACT NO. 76E24							
	PLOT DATE = #DATE#	DATE -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		