

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 90% FED. 10% STATE	-----	-----	CODE NO	ITEM	UNIT		-----	-----	-----
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6									
20400800	FURNISHED EXCAVATION	CU YD	4970	4970									
*25000210	SEEDING, CLASS 2A	ACRE	8	8									
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	720	720									
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	720	720									
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	720	720									
25000700	AGRICULTURAL GROUND LIMESTONE	TON	16	16									
25100115	MULCH, METHOD 2	ACRE	8	8									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800	800									
28000305	TEMPORARY DITCH CHECKS	FOOT	1065	1065									
28000500	INLET AND PIPE PROTECTION	EACH	16	16									
50300225	CONCRETE STRUCTURES	CU YD	26.3	26.3									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2570	2570									
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4									
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1									
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1									
54245005	INLET BOX, STANDARD 542521	EACH	6	6									
54245205	INLET BOX, STANDARD 542511	EACH	3	3									
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1									
54248510	CONCRETE COLLAR	CU YD	1.8	1.8									
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	426	426									
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	394	394									
55101200	STORM SEWER REMOVAL 24"	FOOT	37	37									
60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3									
67100100	MOBILIZATION	L SUM	1	1									
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1									
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18									
X0931400	INLET BOXES TO BE ADJUSTED (SPECIAL)	EACH	1	1									
X6050700	REMOVE INLET BOX	EACH	9	9									
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	30	30									

*SPECIALTY ITEM

FILE NAME =	USER NAME = conoverp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwid\conoverp\vd8207862\vd876630-shit-plan.dgn		DRAWN -	REVISED -			57	61-(1,2,3,4,5,6)-1	MARION	86	4	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 76E30					
PLOT DATE = 2/9/2011		DATE -	REVISED -			SCALE: _____ SHEET NO. 1 OF 1 SHEETS		STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT	